



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 29th, 2026

SUBJECT Various Routes)
Section 2025-2130-TR,LS
Cook County
Contract No. 80C96

Item No. 033, June 12th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i-ii of the Table of Contents of the Special Provisions.
2. Revised page 33 of the Special Provisions.
3. Add page 66 to the Special Provisions.
4. Revised sheets 1-2 of the Plans.
5. Add sheets 113A to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT	1
DESCRIPTION OF IMPROVEMENT	1
COMPLETION DATE	2
LANDSCAPE CONSTRUCTION AND ESTABLISHMENT WORK – INTERIM COMPLETION DATES	2
FAILURE TO COMPLETE LANDSCAPE CONSTRUCTION AND ESTABLISHMENT WORK.....	3
DESCRIPTION OF WORK PHASES.....	4
QUANTITIES.....	5
CONTRACTOR’S SUPERINTENDENT AND CONTRACT COORDINATION	5
CONTRACTOR’S ARBORIST	6
EQUIPMENT	6
LAYOUT MATERIALS	7
TREE REMOVAL AND FORESTRY WORK RESTRICTIONS – ENDANGERED SPECIES ACT	7
SCOPE OF TREE REMOVAL.....	7
TREE REMOVAL (UNDER 6 UNITS DIAMETER).....	8
SELECTIVE CLEARING (ACRE)	9
TREE REMOVAL, ACRES (SPECIAL)	11
TREE REMOVAL (SPECIAL) – WITHIN AREAS DIFFICULT TO ACCESS	13
TREE LIMB REMOVAL (4 TO 10 INCHES DIAMETER)	14
TREE LIMB REMOVAL (OVER 10 INCHES DIAMETER).....	14
PRUNING FOR SAFETY AND EQUIPMENT CLEARANCE	15
STUMP REMOVAL ONLY	16
GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING	16
RESPROUT HERBICIDE.....	18
WEED CONTROL, BASAL TREATMENT	19
WEED CONTROL, BROADLEAF IN TURF (POUND)	21
REQUIRED INSPECTION OF WOODY PLANT MATERIAL.....	22
FAILURE TO COMPLETE PLANTING, PLANT CARE, AND ESTABLISHMENT WORK ON TIME	22
PLANTING WOODY PLANTS	23
WOODY PLANT CARE.....	29
SUPPLEMENTAL WATERING.....	31
MOWING.....	32
TRAFFIC CONTROL PLAN (D1)	33
PUBLIC CONVENIENCE AND SAFETY (D1)	34
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC.....	34
TRAFFIC CONTROL FOR WORK ZONE AREAS	35
TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS).....	35

KEEPING THE EXPRESSWAY OPEN TO TRAFFIC.....	39
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1).....	42
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	42
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (WITH 15 MIN FULL STOPS)	43
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	44
COMPENSABLE DELAY COSTS (BDE).....	45
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	49
ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE).....	51
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	51
SEEDING (BDE)	53
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	58
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	59
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	59
SUBMISSION OF PAYROLL RECORDS – STATE CONTRACT (BDE)	60
SURVEYING SERVICES (BDE)	60
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	61
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	63
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	63
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC.....	66
MAINTENANCE OF ROADWAYS (D1)	66

Method of Measurement: Mowing and trimming will be measured in ACRES of surface area mowed at the completion of each mowing cycle.

Shrub beds or perennial beds within the mowed area that are less than 1000 square feet will not be subtracted from the area mowed.

Basis of Payment: This work will be paid for at the contract unit price per acre for MOWING. Any additional mowing or trimming required to obtain the height specified or to disperse mowed material will be considered as included in the cost of the initial mowing. Payment for mowing and trimming shall include the cost of all material, equipment, labor, removal, disposal, and incidentals required to complete the work as specified herein and to the satisfaction of the Engineer.

TRAFFIC CONTROL PLAN (D1)

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS: 701001, 701006, 701106, 701201, 701301, 701311, 701421, 701422, 701427, 701501, 701502, 701601, 701606, 701611, 701701, 701801, 701901

DETAILS: (TC-08) Entrance and Exit Ramp Closure Details
(TC-10) Traffic Control and Protection for Side Roads, Intersections, and Driveways
(TC-17) Traffic Control and Protection for Freeway Shoulder Closure and Partial Ramp Closure

SPECIAL PROVISIONS:

Public Convenience and Safety (District 1)
Failure to Open Traffic Lanes to Traffic
Traffic Control for Work Zone Areas
Traffic Control and Protection (Expressways)
Keeping the Expressway Open to Traffic
Traffic Control and Protection (Arterials)
Keeping Arterial Roadways Open to Traffic (Lane Closures Only)
Keeping Arterial Roadways Open to Traffic (With 15 Min Full Stops)
Vehicle and Equipment Warning Lights (BDE)
Work Zone Traffic Control Devices (BDE)

Revised 5-29-2026

KEEPING THE EXPRESSWAY OPEN TO TRAFFIC

Effective: March 22, 1996

Revised: January 21, 2015



Whenever work is in progress on or adjacent to an expressway, the Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, the State Standards and the District Freeway details. All Contractors' personnel shall be limited to these barricaded work zones and shall not cross the expressway.

The Contractor shall request and gain approval from the Illinois Department of Transportation's Expressway Traffic Operations Engineer at www.idotlcs.com twenty-four (24) hours in advance of all daily lane, ramp and shoulder closures and 7 days in advance of all permanent and weekend closures on all Freeways and/or Expressways in District One. This advance notification is calculated based on workweek of Monday through Friday and shall not include weekends or Holidays.

Shoulder closures or partial ramp closures (per attached TC-17) will not be permitted on weekdays (Monday thru Friday) from 5:00 a.m. to 9:00 a.m. and from 3:00 p.m. to 7:00 p.m. Lane closures are normally not permitted during the day. Exact hours will be determined by the Expressway Traffic Operations Engineer.

All daily lane closures shall be removed during adverse weather conditions such as rain, snow, and/or fog and as determined by the Engineer.

Additional lane closure hour restrictions may have to be imposed to facilitate the flow of traffic to and from major sporting events and/or other events.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at the locations approved by the Engineer.

MAINTENANCE OF ROADWAYS (D1)

Effective: September 30, 1985

Revised: November 1, 1996

Beginning on the date that work begins on this project, the Contractor shall assume responsibility for normal maintenance of all existing roadways within the limits of the improvement. This normal maintenance shall include all repair work deemed necessary by the Engineer, but shall not include snow removal operations. Traffic control and protection for maintenance of roadways will be provided by the Contractor as required by the Engineer.

If items of work have not been provided in the contract, or otherwise specified for payment, such items, including the accompanying traffic control and protection required by the Engineer, will be paid for in accordance with Article 109.04 of the Standard Specifications.