

* - SPECIALTY ITEM

PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY RECONSTRUCTION	BRIDGE, NEW CONSTRUCTION
				0004	0004
70307120	TEMPORARY PAVEMENT MARKING - LINE 4" - TYPE IV TAPE	FOOT	14,079	14,079	
* 70400100	TEMPORARY CONCRETE BARRIER	FOOT	637.5	637.5	
* 70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,037.5	1,037.5	
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8,723	8,723	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	124	124	
* 78004630	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 6"	FOOT	1,090	1,090	
* 78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1,090	1,090	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
* 78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	3	3	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	2,454	2,454	
* B2000766	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	3	3	
* C2000436	SHRUB, ARONIA ARBUTIFOLIA BRILLIANT ISSIMA (BRILLANT RED CHOKEBERRY), 3' HEIGHT, BALLED AND BURLAPPED	EACH	95	95	
C3006024	SHRUB, RHUS TYPINA (STAGHORN SUMAC), 2' HEIGHT, BARE ROOT	EACH	25	25	1
* K0036118	MULCH PLACEMENT 3"	SQ YD	482	482	
X5420112	ELASTOMERIC CHECK VALVE 12" DIAMETER	EACH	1	1	
X6061462	CLEANING PAVED DITCH	FOOT	147	147	
X6420100	SHOULDER RUMBLE STRIP REMOVAL	SQ YD	826	826	

* SPECIALTY ITEM

1 REVISED SHEET 5/28/2026

MODEL Default
FILE NAME: D:\80D46-500-HR04.dgn

TYLin 200 S. WACKER DR. SUITE 1400 CHICAGO, IL 60606 TEL: 312-777-2900	USER NAME = mark.gormely	DESIGNED - BLG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 41 AT IL 176 INTERCHANGE – ADVANCED DRAINAGE IMPROVEMENTS SUMMARY OF QUANTITIES			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 20,0000 ' / in.	DRAWN - BLG	REVISED -					346	2026-2181-C,HBK	LAKE	60	7
	PLOT DATE = 3/23/2026	CHECKED - MPG	REVISED -		SCALE: N.T.S.			CONTRACT NO. 80D46				
		DATE - 3/20/2026	REVISED -		SHEET 4 OF 5 SHEETS			TO STA. N/A				
										ILLINOIS FED. AID PROJECT		