



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2026

SUBJECT: FAP Route 318 (IL 6)
Project NHPP-4TJZ(351)
Section 72-[6RS;(6-1)RS-1]
Peoria County
Contract No. 68C93
Item No. 84, June 12, 2026 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 90 to the Special Provisions.
4. Revised sheets 4-7, 9-14, 16 and 18 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

PERFORMANCE GRADED ASPHALT BINDER (BDE)	42
PREFORMED PLASTIC PAVEMENT MARKING (BDE)	47
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	48
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	48
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE)	50
SIGN PANELS AND APPURTENANCES (BDE)	53
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	54
SPEED DISPLAY TRAILER (BDE)	55
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	56
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	57
SUBMISSION OF BIDDERS LIST INFORMATION (BDE)	57
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	58
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	59
SURVEYING SERVICES (BDE)	65
TRAINING SPECIAL PROVISIONS (BDE)	65
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	67
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	69
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	69
WORKING DAYS (BDE)	71
PROJECT LABOR AGREEMENT	72
CONCRETE BARRIER WALL REMOVAL AND REPLACEMENT, LOCATION 1	90

CONCRETE BARRIER WALL REMOVAL AND REPLACEMENT, LOCATION 1

This work shall include all labor, equipment, and material required to remove the existing concrete barrier wall and attenuator prior to resurfacing the dead lane and shoulder. The concrete barrier wall shall be stored at a location approved by the Engineer. The concrete barrier wall shall be replaced at this location but the distance from left edge of pavement shall be increased, creating more of a shy line offset. This distance shall be approved by the Engineer. The new impact attenuator shall be placed at approximately the same location and offset as the existing.

This work shall also include all labor, equipment, and material required for the removal and replacement of the existing chevron panels and posts located behind the concrete barrier and the installation of barrier wall reflectors per Standards 704001 and 782006. This work shall be performed to the satisfaction of the Engineer.

Impact attenuators will be paid for separately.

Basis of Payment: This work shall be paid for at the contract unit price per Lump Sum for CONCRETE BARRIER WALL REMOVAL AND REPLACEMENT, LOCATION 1

Added June 2, 2026