

MODEL Default
FILE Name: V:\250559 - Mercer Co IL-Project Planning\2026 Pavement Preservation Project\CADD\CADD Sheets\250559-sh-2-gennote & SOD.dgn

GENERAL NOTES

ALL REFERENCES TO THE "DEPARTMENT" OR "ENGINEER" IN THE IDOT STANDARD SPECIFICATIONS SHALL ALSO INCLUDE THE MERCER COUNTY ENGINEER.

PROPERTY OWNER ACCESS REQUIREMENT

ACCESS MUST BE MAINTAINED TO ALL EXISTING PROPERTIES DURING CONSTRUCTION PER ARTICLE 107.09 UNLESS ARRANGEMENTS ARE MADE IN WRITING BY THE CONTRACTOR WITH THE PROPERTY OWNERS WITH A COPY TO THE ENGINEER FOR SHORT-TERM CLOSURES.

LIST OF HIGHWAY STANDARDS

- 701306-04

LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
- 701901-11

TRAFFIC CONTROL DEVICES
- BLR 18-6

TRAFFIC CONTROL DEVICES - DAY LABOR MAINTENANCE

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
40500061	CAPE SEAL	SQ YD	22670
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	97905
67100100	MOBILIZATION	L SUM	1
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	34633
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
LR403400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	853
LR403500	COVER COAT AGGREGATE	TON	2508
Z0076600	TRAINEES	HOURL	500
LR403600	SEAL COAT AGGREGATE	TON	2508
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	500

*SPECIALTY ITEMS #0042



USER NAME = Shughes	DESIGNED - WSL	REVISED - 06/02/2026
	DRAWN - SRH	REVISED -
PLOT SCALE = 2.000 " / in.	CHECKED - WSL	REVISED -
PLOT DATE = 6/2/2026	DATE - ##-##-26	REVISED -



2026 PAVEMENT PRESERVATION PROGRAM – VARIOUS ROUTES
GENERAL NOTES, LIST OF STANDARDS & SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	26-00000-00-PP	MERCER	6	2
CONTRACT NO. 89892				
ILLINOIS FED. AID PROJECT				

MODEL Default
FILE Name: V:\20059 - Mercer Co IL-Project Planning\2026 Pavement Preservation Project\CADD\CADD Sheets\250059-sh-3-schedules.dgn

PAINT PAVEMENT MARKING - LINE 4"			
LOCATION	78001110		
	4"		
	DOUBLE-SOLID	SOLID	
	YELLOW	WHITE	
	NO PASSING	EDGE LINE	
	CENTERLINE		
FOOT			
LOCATION 3 (CH 2)			
INTERSECTION OF CH 2 & 4TH AVE			
EB	18548	16085	
105'+/- WEST OF CR 3200 E			
SUB-TOTAL		18548	16085
TOTAL		34633	
USE		34633	

PAVEMENT					
LOCATION	40500061	40600275	LR403400	LR403500	LR403600
	CAPE SEAL	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COATS) (2 APPLICATIONS)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE
	SQ YD	POUND	TON	TON	TON
LOCATION 1 (CH 9)					
65'+/- NORTH OF E BEESON ST					
TO			496.38	1459.94	1459.94
MERCER / ROCK ISLAND COUNTY LINE					
LOCATION 2 (CH 16)					
18TH ST IN KEITHSBURG					
TO		97904.93	356.20	1047.66	1047.66
HICKORY ST IN SEATON					
LOCATION 3 (CH 2)					
INTERSECTION OF CH 2 & 4TH AVE					
TO	22669.78				
105'+/- WEST OF CR 3200 E					
TOTAL	22669.78	97904.93	852.58	2507.60	2507.60
USE	22670	97905	853	2508	2508

1



USER NAME = Shughes	DESIGNED - WSL	REVISED - 06/02/2026
DRAWN - SRH	REVISED -	
PLOT SCALE = 2.000 " / in.	CHECKED - WSL	REVISED -
PLOT DATE = 6/2/2026	DATE - ##-##-26	REVISED -



2026 PAVEMENT PRESERVATION PROGRAM – VARIOUS ROUTES
SCHEDULES OF QUANTITIES

SCALE: N/A SHEET 1 OF 1 SHEETS STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	26-00000-00-PP	MERCER	6	3
CONTRACT NO. 89892				
ILLINOIS FED. AID PROJECT				

NOTES:

BITUMINOUS SURFACE TREATMENT A-2 AGGREGATE SHALL E CA-16. APPLICATION RATE SHALL BE 25 LBS/SY.

BITUMINOUS SURFACE TREATMENT A-2 BITUMINOUS MATERIALS SHALL BE PG 52-28. APPLICATION RATE SHALL BE 0.4 GAL/SY.

BITUMINOUS MATERIALS (PRIME COAT) SHALL BE MC-30 AND APPLIED AT A RATE OF 3.07 LBS/SY (0.4 GAL/SY) FROM SEATON TO 14,050' WEST OF SEATON.



END IMPROVEMENT
HICKORY ST



BEGIN IMPROVEMENT
18TH ST

BITUMINOUS SURFACE TREATMENT A-2
LENGTH = (34,287' ± (6.49 MILES))
WIDTH = 22'

MODEL: Default
FILE NAME: V:\2005059 - Mercer Co IL-Project Planning\2026 Pavement Preservation Project\CADD\CADD Sheets\250059-sh-5-plan.dwg



USER NAME = Shughes	DESIGNED - WSL	REVISED - 06/02/2026
	DRAWN - SRH	REVISED -
PLOT SCALE = 4000.000' / in.	CHECKED - WSL	REVISED -
PLOT DATE = 6/2/2026	DATE - ##-##-26	REVISED -



2026 PAVEMENT PRESERVATION PROGRAM – VARIOUS ROUTES LOCATION 2 (CH 16) PLAN			
SCALE: N/A	SHEET 1 OF 1 SHEETS	STA. N/A	TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	26-00000-00-PP	MERCER	6	5
CONTRACT NO. 89892				
ILLINOIS				FED. AID PROJECT