

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 91 (US 150)
MINOR ARTERIAL

RURAL
STA. 178+00.00
STA. 212+55.00

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE:

80% FED / 20% STATE	0010
---------------------	------

	CODE NO.		ITEM	UNIT	TOTAL QUANTITY
	20200100		EARTH EXCAVATION	CU YD	485.00
	20400800		FURNISHED EXCAVATION	CU YD	2,815.00
	21000300		GRANULAR EMBANKMENT, SPECIAL	TON	1,402.00
	25000210		SEEDING, CLASS 2A	ACRE	3.00
	25000400		NITROGEN FERTILIZER NUTRIENT	POUND	270.00
	25000500		PHOSPHORUS FERTILIZER NUTRIENT	POUND	270.00
	25000600		POTASSIUM FERTILIZER NUTRIENT	POUND	270.00
	25100115		MULCH, METHOD 2	ACRE	3.00
	28000250		TEMPORARY EROSION CONTROL SEEDING	POUND	1,200.00
	28000305		TEMPORARY DITCH CHECKS	FOOT	690.00
	28000400		PERIMETER EROSION BARRIER	FOOT	4,336.00
	28000500		INLET AND PIPE PROTECTION	EACH	4.00
	31100100		SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	14.00
	31200100		STABILIZED SUBBASE 4"	SQ YD	231.000
	40200800		AGGREGATE SURFACE COURSE, TYPE B	TON	115.00
* DENOTES SPECIALTY ITEM					

MODEL: SOQ-1 [Sheet]
FILE NAME: c:\pw_work\pwid\pierson\j\d0928965\D570D62-sht-SOQ.dgn

FILE NAME:	USER NAME = Tyler.Pierson	DESIGNED - TJP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - TJP	REVISED -						91	(101)BR	EDGAR	142	4	
		CHECKED -	REVISED -							CONTRACT NO. 70D62				
	PLOT DATE = 3/10/2026	DATE	REVISED -		SCALE:	SHEET 1	OF 9 SHEETS	STA. TO STA.						
								ILLINOIS FED. AID PROJECT						

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 91 (US 150)
MINOR ARTERIAL

RURAL
STA. 178+00.00
STA. 212+55.00
EDGAR
80% FED / 20% STATE

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

0010

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY
	40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	5,948.00
	40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	8,975.00
	40600370	LONGITUDINAL JOINT SEALANT	FOOT	3,069.00
	40600405	MATERJAL TRANSFER DEVICE	TON	2,668.00
	40600990	TEMPORARY RAMP	SQ YD	99.00
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,214.00
	40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	478.00
	40604160	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	1,334.00
	40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	262.00
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	49.00
	42000060	WELDED WIRE REINFORCEMENT	SQ YD	264.00
	42000080	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB	SQ YD	264.00
	44000100	PAVEMENT REMOVAL	SQ YD	457.00
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	3,798.00
	44000182	HOT-MIX ASPHALT SURFACE REMOVAL, 8"	SQ YD	1,454.00
* DENOTES SPECIALTY ITEM				

1

MODEL: SQO-2 [Sheet]
FILE NAME: c:\pw_work\pierson\0928065\0570D62-shl-SQO.dgn