



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 1st, 2026

SUBJECT FAP Route 666A (I-55 BUS)
Project NHPP-Q9S9(347)
Section 27RS-7, TS-3; 26RS-1
Sangamon County
Contract No. 72491

Item No. 112, June 12th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised pages i-ii of the Table of Contents of the Special Provisions.
3. Revised page 31 of the Special Provisions.
4. Revised sheets 1, 8, 34, 89, and 91-93 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	2
STATUS OF UTILITIES TO BE ADJUSTED	5
UNDERGROUND FACILITIES – DEPARTMENT OWNED	8
CHANGEABLE MESSAGE SIGN	8
HMA SURFACE REMOVAL, 1 1/2"	9
HMA ANTI-STRIP ADDITIVE REQUIREMENTS	9
PAVEMENT STATIONING NUMBERS AND PLACEMENT	10
GUARDRAIL REMOVAL (SPECIAL)	10
AGGREGATE SHOULDERS (SPECIAL)	11
CONCRETE CURB REPAIR	11
CONCRETE MEDIAN SURFACE REMOVAL	12
CORRUGATED MEDIAN REMOVAL	12
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	12
REMOVE AND REINSTALL SIGN PANEL	13
CONE PENETRATION TEST DATA	13
REMOVE EXISTING SERVICE INSTALLATION	14
INTERCEPT EXISTING CONDUIT	14
CONCRETE FOUNDATION (SPECIAL)	14
HANDHOLE	15
FULL-ACTUATED CONTROLLER	15
ETHERNET SWITCH	17
COMBINATION LIGHTING CONTROLLER	20
FIBER OPTIC CABLE 24 FIBERS, SINGLE MODE	21
PEDESTRIAN PUSH-BUTTON POST	24
RAILROAD INTERCONNECT CABLE	24
SPARE RAILROAD, FULL ACTUATED CONTROLLER, SPECIAL	25
VIDEO VEHICLE DETECTION SYSTEM, 3 CAMERA	28
VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERA	29
RAILROAD INTERCONNECT CABLE	31
ACCESSIBLE PEDESTRIAN SIGNALS (APS) (BDE)	32
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	33
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	34

CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE).....	35
COMPENSABLE DELAY COSTS (BDE).....	50
FUEL COST ADJUSTMENT (BDE).....	54
GUARDRAIL (BDE)	56
HOT-MIX ASPHALT (BDE).....	56
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	60
PAVEMENT MARKING (BDE).....	61
PAVEMENT PATCHING (BDE).....	61
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	62
RAISED REFLECTIVE PAVEMENT MARKERS (BDE).....	67
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	67
SEEDING (BDE)	69
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	74
SIGN PANELS AND APPURTENANCES (BDE).....	77
SINUSOIDAL RUMBLE STRIPS (BDE)	78
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	79
STEEL COST ADJUSTMENT (BDE).....	81
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	82
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	83
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	83
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE).....	84
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	85
SURVEYING SERVICES (BDE).....	91
TRAFFIC SIGNAL BACKPLATE (BDE).....	91
TRAINING SPECIAL PROVISIONS (BDE)	92
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	94
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	96
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	96
PROJECT LABOR AGREEMENT	99

Basis of Payment. This work will be paid for at the contract unit price per EACH for VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERA which shall include all labor, equipment, cable, brackets and any other material required to complete the work to the intended function.

RAILROAD INTERCONNECT CABLE.

The cable shall meet the requirements of Section 873 of the Standard Specifications, except for the following:

Add to Article 873.02 of the Standard Specifications:

The railroad interconnect cable shall be three conductor stranded #14 copper cable in a clear polyester binder, with each conductor individually shielded with #36 AWG tinned copper braid with 85% coverage, and insulated with .016" polyethylene (black, blue, red). The jacket shall be black 0.045 PVC or polyethylene.

Add the following to Article 873.05 of the Standard Specifications:

Basis of Payment. This work shall be paid for at the contract unit price per FOOT for ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C, which price shall be payment in full for furnishing, installing, and making all electrical connections in the traffic signal controller cabinet. Connections in the railroad controller cabinet shall be performed by railroad personnel.

