

MODEL: Quantities 4 [Sheet]
FILE NAME: P:\5XXX\52XX-53XX\5289 - PTB 201-1037 D7 VV_HLR\Work Order #3\CADD Data\Sheet\074705-sh1-SQO.dgn



USER NAME = kulrich	DESIGNED -	REVISED -
	DRAWN -	REVISED -
	CHECKED -	REVISED -
PLOT DATE = 8/20/2025	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 4 OF 5 SHEETS STA. TO STA.

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(58-63 HVB) BR	MACON	122	6
CONTRACT NO. 74705				
ILLINOIS FED. AID PROJECT				

1 REVISED 5-28-2026

REV - MS

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				BRIDGE 0010	BRIDGE 0010
				S.N. 058-0139	S.N. 058-0140
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	2	2
* 78004630	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 6"	FOOT	3474	1787	1687
* 78004640	PREFORMED PLASTIC PAVEMENT MARKING, TYPE D - STANDARD - LINE 8"	FOOT	480	315	165
* 78011035	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	3474	1787	1687
* 78011045	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	480	315	165
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	33	25	8
* 78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	19	10	9
78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	32	17	15
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	22	22	
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	13042	5730	7312
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.75	0.38	0.37
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	270	66	204
	* SPECIALTY ITEM				

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				90% FEDERAL 10% STATE	90% FEDERAL 10% STATE
				BRIDGE 0010	BRIDGE 0010
				S.N. 058-0139	S.N. 058-0140
X5030250	BRIDGE DECK GROOVING (LONGITUDINAL)	SQ YD	3329	1487	1842
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	873	414	459
X5040100	PRECAST BRIDGE APPROACH SLAB	SQ FT	7531	3571	3960
X5080530	BAR TERMINATORS	EACH	1246	590	656
X5230174	DRAINAGE SCUPPERS, DS-11	EACH	8	4	4
X6050208	FILLING EXISTING CULVERTS	CU YD	10	10	
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	1	1
X7200203	DETOUR SIGNING	L SUM	1	0.5	0.5
X7810400	TEMPORARY RAISED PAVEMENT MARKER	EACH	672	450	222
X7830050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	21	21	
Z0029090	DIAMOND GRINDING (BRIDGE SECTION)	SQ YD	4301	2025	2276
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5
Z0049799	PROTECTING OR RESETTNG SURVEY MARKERS	EACH	2	1	1
Z0062456	TEMPORARY PAVEMENT	SQ YD	270	66	204
	* SPECIALTY ITEM				