



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 5, 2026

SUBJECT Various Routes
Project STP-0PS4(714)
Section Dist 8 TS Replace 2026-1
Madison and St. Clair Counties
Contract No. 76U38

Item No. 153, June 12th, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised pages ii of the Table of Contents of the Special Provisions.
3. Add pages 66-67 to the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

VARIOUS ROUTES
PROJECT STP-0PS4(714)
SECTION DIST 8 TS REPLACE 2026-1
MADISON AND ST. CLAIR COUNTIES
CONTRACT NO. 76U38

SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE) 60

SURVEYING SERVICES (BDE)..... 62

TRAFFIC SIGNAL BACKPLATE (BDE)..... 62

VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 62

WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 63

WORKING DAYS (BDE) 65

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 66

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Work Areas. For stationing, the lateral distance is measured from the centerline, and the farthest distance is the offset distance or construction limit, whichever is less.

The following contract-specific work areas shall be monitored by the Environmental Firm for soil contamination and workers' protection.

ISGS PESA 4871-6 Commercial Buildings, 511 to 515 Falling Springs Road, Dupon, St. Clair County, Illinois

- Station 99+25 to Station 99+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-9 St. Clair County Highway Department, 1405 North Belt West, Swansea, St. Clair County, Illinois

- Station 99+25 to Station 99+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-12 MotoMart, 2235 IL 161, Belleville, St. Clair County, Illinois

- Station 25+00 to Station 25+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-13 Commercial Building, 8 Fullerton Road, Swansea, St. Clair County, Illinois

- Station 27+00 to Station 28+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-14 Commercial Building, 1 to 8 Wade Square, Belleville, St. Clair County, Illinois

- Station 253+00 to Station 254+00. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-15 Phillips 66 Gasoline Station, 1257 Lebanon Avenue, Belleville, St. Clair County, Illinois

- Station 254+00 to Station 255+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.
- Station 61+00. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-17 Save-On Liquor & Wine, 1260 Lebanon Avenue, Belleville, St. Clair County, Illinois

- Station 60+50 to Station 61+00. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-21 Residence, 1309 Lebanon Avenue, Belleville, St. Clair County, Illinois

- Station 255+00 to Station 255+50. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-23 Residence, 1304 Lebanon Avenue, Belleville, St. Clair County, Illinois

- Station 256+50 to Station 259+00. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-29 Great Rivers Flood Memorial, 100 Block of W. Broadway, Alton, Madison, Illinois

- Station 49+50 to Station 49+75. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-35 Rustic Roots, 200 W. Ferguson Avenue, Wood River, Madison, Illinois

- Station -2+00 to Station -21+25. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.

ISGS PESA 4871-38 Vacant Lot, 0 to 99 Block of Madison Avenue, Wood River, Madison, Illinois

- Station -0+50 to Station +0+25. The Engineer has determined that all excavation related to this contract work shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters include: VOCs, SVOCs, and metals.
 - o Due to the site being listed as an Archived SEMS, a construction worker caution has been put in place. The site is connected to the "Wood River Terminal." Exceedances of established Tier 2 Soil and groundwater remediation objectives are noted for benzene, BTEX, PAHs, and metals. An existing engineered control, worker safety plan, commercial/industrial land-use restrictions, and groundwater-use restrictions are in effect for this PESA site.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply to the following ISGS PESA Sites: Vacant Lot (PESA Site 4871-38)

Additional information on the contract-specific work areas listed above, collected during the regulated substances due diligence process, is available through the District's Environmental Studies Unit (DESU).