

MODEL: SQQ [Sheet]
FILE NAME: c:\pw\work\pwid\matthew.wilson@illinois.gov\1197521\0978C25-SQQ.dgn

SUMMARY OF QUANTITIES			COUNTY:	PERRY CO
			ROUTE:	FAP 861
			FUNDING:	80% FEDERAL 20% STATE
			LOCATION:	RURAL
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY
				0005
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	26,648	26,648
40600370	LONGITUDINAL JOINT SEALANT	FOOT	14,905	14,905
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600405	MATERIAL TRANSFER DEVICE	TON	6,535	6,535
40600990	TEMPORARY RAMP	SQ YD	56	56
40602970	HOT-MIX ASPHALT BINDER COURSE, IL-9.5FG, N70	TON	3,276	3,276
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	3,411	3,411
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8	8
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	39,922	39,922
44201411	CLASS C PATCHES, TYPE I, 15 INCH	SQ YD	37	37
44201415	CLASS C PATCHES, TYPE II, 15 INCH	SQ YD	1920	1920
44201419	CLASS C PATCHES, TYPE III, 15 INCH	SQ YD	199	199
44201421	CLASS C PATCHES, TYPE IV, 15 INCH	SQ YD	623	623
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	828	828
64200214	SINUSOIDAL RUMBLE STRIPS, 14"	FOOT	14,905	14,905



REV. 6-5-26

REV - MS

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			861	111RS-4	Perry	19	5
			CONTRACT NO. 78C25				
			ILLINOIS FED. AID PROJECT				
USER NAME = Matthew.Wilson	DESIGNED -	REVISED -	SCALE:				
	DRAWN -	REVISED -	SHEET 5 OF 19 SHEETS				
	CHECKED -	REVISED -	STA. TO STA.				
PLOT DATE = 3/12/2026	DATE -	REVISED -					

MODEL: Patching 2 (Sheet)
FILE NAME: c:\p\work\pwtol\matthew.wilson@illinois.gov\117521\0578C25-Schedules.dgn

PATCHING SCHEDULE- CONT'D							
LOCATION NB IL 150			AREA	CLASS C PATCHING, TY I 15 INCH	CLASS C PATCHING, TY II 15 INCH	CLASS C PATCHING, TY III 15 INCH	CLASS C PATCHING, TY IV 15 INCH
PATCH #	WIDTH	LENGTH	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
101	12	8	10.67	0.00	10.67	0.00	0.00
102	12	10	13.33	0.00	13.33	0.00	0.00
103	6	6	4.00	4.00	0.00	0.00	0.00
104	12	8	10.67	0.00	10.67	0.00	0.00
105	12	10	13.33	0.00	13.33	0.00	0.00
106	12	8	10.67	0.00	10.67	0.00	0.00
107	12	8	10.67	0.00	10.67	0.00	0.00
108	12	6	8.00	0.00	8.00	0.00	0.00
109	12	6	8.00	0.00	8.00	0.00	0.00
110	12	7	9.33	0.00	9.33	0.00	0.00
111	12	6	8.00	0.00	8.00	0.00	0.00
112	12	8	10.67	0.00	10.67	0.00	0.00
113	12	10	13.33	0.00	13.33	0.00	0.00
114	12	12	16.00	0.00	0.00	16.00	0.00
115	12	6	8.00	0.00	8.00	0.00	0.00
116	12	7	9.33	0.00	9.33	0.00	0.00
117	12	12	16.00	0.00	0.00	16.00	0.00
118	12	6	8.00	0.00	8.00	0.00	0.00
119	12	8	10.67	0.00	10.67	0.00	0.00
120	12	6	8.00	0.00	8.00	0.00	0.00
121	12	12	16.00	0.00	0.00	16.00	0.00
122	12	7	9.33	0.00	9.33	0.00	0.00
123	12	6	8.00	0.00	8.00	0.00	0.00
124	12	7	9.33	0.00	9.33	0.00	0.00
125	12	8	10.67	0.00	10.67	0.00	0.00
126	12	6	8.00	0	8	0	0
NB IL 150 TOTALS:			1652.00	13	996	116	531
GROWTH FACTOR:		10%	165.20	2	100	12	54
TOTAL WITH GROWTH FACTOR:			1817.20	15	1096	128	585

PATCHING SCHEDULE							
LOCATION SB IL150			AREA	CLASS C PATCHING, TY I 15 INCH	CLASS C PATCHING, TY II 15 INCH	CLASS C PATCHING, TY III 15 INCH	CLASS C PATCHING, TY IV 15 INCH
PATCH #	WIDTH	LENGTH	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
1	12	8	10.67	0.00	10.67	0.00	0.00
2	12	6	8.00	0.00	8.00	0.00	0.00
3	12	8	10.67	0.00	10.67	0.00	0.00
4	6	6	4.00	4.00	0.00	0.00	0.00
5	12	6	8.00	0.00	8.00	0.00	0.00
6	12	6	8.00	0.00	8.00	0.00	0.00
7	12	6	8.00	0.00	8.00	0.00	0.00
8	12	6	8.00	0.00	8.00	0.00	0.00
9	3	10	3.33	3.33	0.00	0.00	0.00
10	12	6	8.00	0.00	8.00	0.00	0.00
11	6	6	4.00	4.00	0.00	0.00	0.00
12	12	7	9.33	0.00	9.33	0.00	0.00
13	6	10	6.67	0.00	6.67	0.00	0.00
14	12	6	8.00	0.00	8.00	0.00	0.00
15	12	6	8.00	0.00	8.00	0.00	0.00
16	12	6	8.00	0.00	8.00	0.00	0.00
17	12	12	16.00	0.00	0.00	16.00	0.00
18	12	8	10.67	0.00	10.67	0.00	0.00
19	12	6	8.00	0.00	8.00	0.00	0.00
20	12	6	8.00	0.00	8.00	0.00	0.00
21	12	8	10.67	0.00	10.67	0.00	0.00
22	12	6	8.00	0.00	8.00	0.00	0.00
23	12	6	8.00	0.00	8.00	0.00	0.00
24	12	6	8.00	0.00	8.00	0.00	0.00
25	12	10	13.33	0.00	13.33	0.00	0.00
SUB-TOTALS				12	184	16	0

MODEL: Patching Schedule 4 [Sheet]
FILE NAME: c:\pa_work\wtd\matthew.wilson@illinois.gov\117521UD878C25-Schedules.dgn

PATCHING SCHEDULE- CONT'D							
LOCATION SB IL 150			AREA	CLASS C PATCHING, TY I 15 INCH	CLASS C PATCHING, TY II 15 INCH	CLASS C PATCHING, TY III 15 INCH	CLASS C PATCHING, TY IV 15 INCH
PATCH #	WIDTH	LENGTH	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
73			0.00	0.00	0.00	0.00	0.00
74	12	6	8.00	0.00	8.00	0.00	0.00
75	12	6	8.00	0.00	8.00	0.00	0.00
76	12	6	8.00	0.00	8.00	0.00	0.00
77	12	7	9.33	0.00	9.33	0.00	0.00
78	12	6	8.00	0.00	8.00	0.00	0.00
79	12	6	8.00	0.00	8.00	0.00	0.00
80	12	6	8.00	0.00	8.00	0.00	0.00
81	12	6	8.00	0.00	8.00	0.00	0.00
82	12	8	10.67	0.00	10.67	0.00	0.00
83	12	7	9.33	0.00	9.33	0.00	0.00
84	12	10	13.33	0.00	13.33	0.00	0.00
85	12	10	13.33	0.00	13.33	0.00	0.00
86	12	6	8.00	0.00	8.00	0.00	0.00
87	12	6	8.00	0.00	8.00	0.00	0.00
88	12	8	10.67	0.00	10.67	0.00	0.00
89	12	8	10.67	0.00	10.67	0.00	0.00
90	12	6	8.00	0.00	8.00	0.00	0.00
91	12	7	9.33	0.00	9.33	0.00	0.00
92	12	7	9.33	0.00	9.33	0.00	0.00
93	12	7	9.33	0.00	9.33	0.00	0.00
94	12	6	8.00	0.00	8.00	0.00	0.00
95	15	20	33.33	0.00	0.00	0.00	33.33
SB IL 150 TOTALS:			864.67	20	749	64	34
GROWTH FACTOR			10%	86.47	2	75	4
TOTAL WITH GROWTH FACTOR:			951.13	22	824	71	38
IL 150 TOTALS				37	1920	199	623



1 rev. 6-5-26

	USER NAME = Matthew.Wilson	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE			F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -					861	111RS-4	Perry	19	14
		CHECKED -	REVISED -					CONTRACT NO. 78C25				
	PLOT DATE = 6/2/2026	DATE -	REVISED -		SCALE:	SHEET 14	OF 19 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		