

CONTRACT NO. 99748

* SPECIALTY ITEM

c:\MARILCZ\230132000-Marion Safe Routes to Lincoln School\01_CADD\Maril\Drawings - Plans\03 SQQ.dwg 4-02-25 04:43:18 PM mkkrumrey

P:\MAR16\230132000-Marion Safe Routes to Lincoln School\01_CADD\Marion Drawings - Plans\05-06 SCHEDULES.dwg 6-01-26 02:30:37 PM mkkurney

SIDEWALK & DRIVEWAY SCHEDULE

LOCATION STATION TO STATION	42400200		42400800		60600605	42300200
	PCC SIDEWALK 5 INCH		DETECTABLE WARNINGS		CONCRETE CURB, TYPE B	PCC DRIVEWAY PAVEMENT, 8 INCH
	SQ FT		SQ FT		FOOT	SQ YD
FAIR STREET						
IL 13 TO PATTON DRIVE						
RT 0+42 TO RT 0+50	39		8			
RT 0+50 TO RT 0+97	232					
RT 0+97 TO RT 1+12	62		8			
RT 1+41 TO RT 1+57	73		10			
RT 1+57 TO RT 3+00	727					
RT 3+00 TO RT 3+33	168					
RT 3+33 TO RT 3+44	50		10			
RT 4+00 TO RT 4+10	49		10			
RT 4+10 TO RT 6+00	953					
RT 6+00 TO RT 6+26	120					
RT 6+26 TO RT 6+38	66		10			
PATTON DRIVE TO ILLINOIS STREET						
RT 6+71 TO RT 6+83	65		10			
RT 6+83 TO RT 8+46	763					
RT 8+46 TO RT 8+59	61		10			
ILLINOIS STREET TO MIDBLOCK CROSSING						
RT 8+98 TO RT 9+00	24		10			
RT 9+00 TO RT 9+09	39					
RT 9+09 TO RT 9+68	274					
RT 9+68 TO RT 9+75	108		10			
MIDBLOCK CROSSING TO CLARK STREET						
LT 9+75 TO LT 9+82	68		10			
LT 9+82 TO LT 12+00	1068			222		
LT 12+00 TO LT 12+25	173			25		
LT 12+25 TO LT 12+38			17			
CLARK STREET TO GREGORY STREET						
LT 12+66 TO LT 12+79	41		18			
LT 12+79 TO LT 13+89	549			113		
PE LT 13+89 TO LT 14+29						50
LT 14+29 TO LT 15+00	354			71		
LT 15+00 TO LT 15+87	453			87		
LT 15+87 TO LT 15+99	25		16			
GREGORY STREET TO MORNINGSIDE DRIVE						
LT 16+39 TO LT 16+51	35		20			
LT 16+51 TO LT 18+00	750			150		
LT 18+00 TO LT 18+73	367			73		
PE LT 18+73 TO LT 18+95						29
LT 18+95 TO LT 19+31	189			25		
MORNINGSIDE DRIVE						
FAIR STREET REVELLE ROAD						
LT 19+74 TO LT 20+99	490					
PEL 20+99 TO PEL 21+22						24
LT 21+22 TO LT 21+85	253					
PEL 21+85 TO PEL 22+08						21
LT 22+08 TO LT 23+22	458					
PEL 23+22 TO PEL 23+44						22
LT 23+44 TO LT 24+08	259					
PEL 24+08 TO PEL 24+28						20
LT 24+28 TO LT 25+06	310					
PEL 25+06 TO PEL 25+24						20
LT 25+24 TO LT 25+94	279					
PEL 25+94 TO PEL 26+16						23
LT 26+16 TO LT 26+76	240					
PEL 26+76 TO PEL 26+99						23
LT 26+99 TO LT 27+82	340					
PROJECT TOTAL						
	10,574		177		766	232




REMOVAL SCHEDULE

LOCATION: STATION TO STATION	44000200	44000500	50105220
	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB & GUTTER REMOVAL	PIPE CULVERT REMOVAL
	SQ YD	FOOT	FOOT
FAIR STREET			
RT 0+43		10	
RT 1+10		10	
RT 1+40		10	
PE LT 13+89 TO LT 14+29	50		
PE LT 18+73 TO LT 18+95	29		24
MORNINGSIDE DRIVE			
PE LT 20+99 TO LT 21+22	24		
PE LT 21+85 TO LT 22+08	21		
PE LT 23+22 TO LT 23+44	22		
PE LT 24+08 TO LT 24+28	20		
PE LT 25+06 TO LT 25+24	20		
PE LT 25+94 TO LT 26+16	23		
PE LT 26+76 TO LT 26+99	23		
PROJECT TOTAL			
	232	30	24

PAVEMENT MARKING

LOCATION STATION TO STATION	78001150
	PAINT PAVEMENT MARKING - LINE 12"
	FOOT
FAIR STREET	
LT 0+42 TO RT 0+42	152
PATTON STREET	64
EAST ILLINOIS STREET	56
LT 9+75 TO RT 9+75	48
EAST CLARK STREET	48
EAST GREGORY STREET	68
PROJECT TOTAL	
	436

DETAIL
PAINT PAVEMENT MARKING - LINE 12"



STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184000435-0014			
REVISIONS		© 2023 ALL RIGHTS RESERVED	
DATE	NO.		
6-2-26	1		
		SCHEDULE	
		N. FAIR ST. & MORNINGSIDE DR. SAFE ROUTES TO SCHOOL	
		CITY OF MARION, ILLINOIS	
Date	MARCH/2026	DR. By	MKK
		CK'D By	JVZ
Scale	N.T.S.	Job No.	230132000
		Sheet No.	06 of 41

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MUN 1060D MUN 1026	24-00132 -00-SW	WILLIAMSON	41	06
ILLINOIS		N.FAIR & MORNINGSIDE DR.		

CONTRACT NO. 99748