



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 26, 2026

SUBJECT FAU Route 3587 (Main Street)
Project STP-9RBL(870)
Section 2020-142-C&DR
Cook County
Contract No. 62L30
Item No. 212, June 12, 2026, Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions
2. Added pages 169 & 177 to the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

AGGREGATE SUBGRADE IMPROVEMENT (BDE).....	62
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)	64
CEMENT, FINELY DIVIDED MINERALS, ADMIXTURES, CONCRETE, AND MORTAR (BDE)	66
COMPENSABLE DELAY COSTS (BDE).....	82
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	86
EROSION CONTROL BLANKET (BDE).....	88
FUEL COST ADJUSTMENT (BDE)	90
GUARDRAIL (BDE).....	93
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)	93
INLET FILTERS.....	94
PAVEMENT MARKING (BDE)	96
PAVEMENT PATCHING (BDE)	97
PERFORMANCE GRADED ASPHALT BINDER (BDE)	97
RAISED REFLECTIVE PAVEMENT MARKERS (BDE)	103
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE).....	103
SEEDING (BDE)	105
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	110
SIGN PANELS AND APPURTENANCES (BDE)	114
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE).....	115
STEEL COST ADJUSTMENT (BDE)	116
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	118
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	119
SUBMISSION OF BIDDERS LIST INFORMATION (BDE).....	119
SUBMISSION OF PAYROLL RECORDS – FEDERAL AID CONTRACT (BDE)	120
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	122
SURVEYING SERVICES (BDE).....	128
TRAINING SPECIAL PROVISIONS (BDE).....	128
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	131
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....	133
WATERPROOFING MEMBRANE SYSTEM (BDE).....	133
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	133
STORM WATER POLLUTION PREVENTION PLAN	136
PROJECT LABOR AGREEMENT.....	150
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	169

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Sites. The excavated soil and groundwater within the areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

Site 3256V-1: Railroad, 1000-14000 blocks of Main Street, Lemont, Cook County

- Station 9+50 to Station 12+60 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.
- Station 15+20 to Station 18+45 (CL Main Street), 0 to 45 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 21+55 to Station 24+40 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.
- Station 24+40 to Station 27+40 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, Arsenic, and Manganese.
- Station 27+40 to Station 30+50 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Dibenzo(a,h)anthracene, Arsenic, and Manganese.
- Station 30+50 to Station 34+00 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.

Site 3256V-3: Vacant Land, 1000 block of Main Street, Lemont, Cook County

- Station 9+50 to Station 9+95 (CL Main Street), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Manganese.

Site 3256V-4: Vacant Land, 14800-14900 blocks of Main Street, Lemont, Cook County

- Station 9+95 to Station 11+05 (CL Main Street), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Manganese.
- Station 11+05 to Station 13+80 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, Indeno(1,2,3- cd)pyrene, and Lead.
- Station 13+80 to Station 16+95 (CL Main Street), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Lead, and Manganese.
- Station 16+95 to Station 19+95 (CL Main Street), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Lead, and Manganese.
- Station 19+95 to Station 23+00 (CL Main Street), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.
- Station 23+00 to Station 25+55 (CL Main Street), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, and Dibenzo(a,h)anthracene.

Site 3256V-5: Vacant Land, 14500-14700 blocks of Main Street, Lemont, Cook County

- Station 25+55 to Station 26+05 (CL Main Street), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, and Dibenzo(a,h)anthracene.
- Station 26+05 to Station 29+05 (CL Main Street), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: pH, Benzo(a)pyrene, Lead, and Manganese.

- Station 29+05 to Station 32+00 (CL Main Street), 0 to 50 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Dibenzo(a,h)anthracene, Arsenic, and Lead.
- Station 32+00 to Station 35+15 (CL Main Street), 0 to 85 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Manganese.
- Station 35+15 to Station 38+55 (CL Main Street), 0 to 65 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article Arsenic, and Manganese.

Site 3256V-10: Franciscan Village, 1260-1270 Franciscan Drive, Lemont, Cook County

- Station 53+45 to Station 55+95 (CL Main Street), 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Manganese.
- Station 55+95 to Station 58+75 (CL Main Street), 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Dibenzo(a,h)anthracene.
- Station 58+75 to Station 60+50 (CL Main Street), 0 to 55 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Manganese.
- Station 200+00 to Station 200+65 (CL Walker Road), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Manganese.

Site 3256V-11: Vacant Land, 14300-14600 blocks of Main Street, Lemont, Cook County

- Station 47+65 to Station 51+45 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 54+50 to Station 57+55 (CL Main Street), 0 to 30 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 57+55 to Station 60+25 (CL Main Street), 0 to 45 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 60+25 to Station 63+20 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Dibenzo(a,h)anthracene.

- Station 63+20 to Station 65+50 (CL Main Street), 0 to 60 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Indeno(1,2,3-cd)pyrene.

Site 3256V-12: Vacant Land, 14400 block of Main Street, Lemont, Cook County

- Station 60+85 to Station 62+35 (CL Main Street), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.
- Station 200+00 to Station 200+65 (CL Walker Road), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.
- Station 62+35 to Station 63+55 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminant of concern sampling parameter: Arsenic.

Site 3256V-13: Residence, 14310 Main Street, Lemont, Cook County

- Station 63+55 to Station 64+20 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminant of concern sampling parameter: Arsenic.
- Station 64+20 to Station 65+50 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Site 3256V-14: Unnamed Tributary to the Sanitary and Ship Canal, 14300 block of Main Street, Lemont, Cook County

- Station 65+50 to Station 67+00 (CL Main Street), 0 to 60 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, and Indeno(1,2,3-cd)pyrene.
- Station 65+50 to Station 66+00 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Site 3256V-16: St. Mary's Franciscan Monastery, 14230-14246 Main Street, Lemont, Cook County

- Station 66+00 to Station 68+55 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminant of concern sampling parameter: Manganese.
- Station 68+55 to Station 71+35 (CL Main Street), 0 to 30 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 71+35 to Station 74+10 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameter: Manganese.
- Station 74+10 to Station 77+15 (CL Main Street), 0 to 45 feet RT, and 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 77+15 to Station 80+15 (CL Main Street), 0 to 35 feet RT, and 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.
- Station 80+15 to Station 83+00 (CL Main Street), 0 to 35 feet RT, and 0 to 65 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 83+00 to Station 86+15 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 3256V-17: Mt. Assisi Center, 13820-13950 Main Street, Lemont, Cook County

- Station 89+10 to Station 92+30 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Carbazole, Dibenzo(a,h)anthracene, Indeno(1,2,3-cd)pyrene, and Manganese.
- Station 92+30 to Station 95+30 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 95+30 to Station 98+20 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Manganese.

Site 3256V-18: Vacant Land, 13700-14200 blocks of Main Street, Lemont, Cook County

- Station 86+50 to Station 88+70 (CL Main Street), 0 to 55 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminant of concern sampling parameter: Arsenic.
- Station 88+70 to Station 91+30 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 91+30 to Station 93+50 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Dibenzo(a,h)anthracene, and Arsenic.

Site 3256V-19: K-Five Construction Corporation, 13751-13769 Main Street, Lemont, Cook County

- Station 111+50 to Station 115+10 (CL Main Street), 0 to 55 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, and Manganese.

Site 3256V-20: Illini Hi-Reach, 13633 Main Street, Lemont, Cook County

- Station 115+10 to Station 118+10 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.

Site 3256V-22: Blue Duck Semi Truck Tire, 13555 Main Street, Lemont, Cook County

- Station 124+70 to Station 127+55 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminant of concern sampling parameter: Benzo(a)pyrene.

Site 3256V-24 – Cog Hill County Club, 12294 Archer Avenue, Lemont, Cook County

- Station 104+20 to Station 111+25 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminant of concern sampling parameter: Arsenic.
- Station 111+25 to Station 113+40 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminant of concern sampling parameter: Benzo(a)pyrene.
- Station 119+00 to Station 122+10 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, Indeno(1,2,3-cd)pyrene, and Lead.
- Station 133+30 to Station 136+20 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminant of concern sampling parameter: Benzo(a)pyrene.
- Station 136+20 to Station 142+00 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 150+30 to Station 155+20 (CL Main Street), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameter: Manganese.

Site 3256V-25: NTS Trailer Services, Inc., 13333 Main Street, Lemont, Cook County

- Station 127+55 to Station 130+65 (CL Main Street), 0 to 45 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.
- Station 130+65 to Station 133+95 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Cadmium, Lead, and Manganese.

Site 3256V-26: Ahern Rentals, 13275 Main Street, Lemont, Cook County

- Station 143+20 to Station 145+00 (CL Main Street), 0 to 30 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Lead, and Manganese.

Site 3256V-27: Vacant Land, 13200 block of Main Street, Lemont, Cook County

- Station 145+00 to Station 146+35 (CL Main Street), 0 to 30 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Benzo(a)pyrene, Lead, and Manganese.
- Station 146+35 to Station 151+70 (CL Main Street), 0 to 45 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.

Site 3256V-28: Total Transportation & Logistics, 13089 Main Street, Lemont, Cook County

- Station 151+70 to Station 152+00 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 152+00 to Station 154+10 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.
- Station 154+10 to Station 154+20 (CL Main Street), 0 to 35 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Arsenic.

Site 3256V-29: Green APU, 13067 Main Street, Lemont, Cook County

- Station 154+20 to Station 156+20 (CL Main Street), 0 to 40 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, and Arsenic.
- Station 156+20 to Station 158+30 (CL Main Street), 0 to 30 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)anthracene, Benzo(a)pyrene, Benzo(b)fluoranthene, Dibenzo(a,h)anthracene, Indeno(1,2,3-cd)pyrene, and Lead.

Site 3256V-30: Residences, 13130-13150 Main Street, Lemont, Cook County

- Station 144+70 to Station 147+45 (CL Main Street), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminant of concern sampling parameter: Manganese.
- Station 147+45 to Station 149+95 (CL Main Street), 0 to 40 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Arsenic, Lead, and Manganese.
- Station 149+95 to Station 150+30 (CL Main Street), 0 to 35 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminant of concern sampling parameter: Manganese.

Site 3256V-31: Residence, 13000 Main Street, Lemont, Cook County

- Station 157+20 to Station 158+30 (CL Main Street), 0 to 45 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, Lead, and Manganese.

Site 3256V-32: Utility Corridor, 13000 block of Main Street, Lemont, Cook County

- Station 158+30 to Station 159+75 (CL Main Street), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.

Site 3256V-33: Utility Corridor, 13000 block of Main Street, Lemont, Cook County

- Station 158+30 to Station 158+90 (CL Main Street), 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(1). Contaminants of concern sampling parameters: Arsenic, Lead, and Manganese.
- Station 158+90 to Station 159+75 (CL Main Street), 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.

Site 3256V-35: Chicago Brick and Stone, 10800 IL 83, Lemont, Cook County

- Station 159+75 to Station 161+05 (CL Main Street), 0 to 50 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.
- Station 161+05 to Station 165+30 (CL Main Street), 0 to 75 feet LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(3). Contaminants of concern sampling parameters: Benzo(a)pyrene, Arsenic, Lead, and Manganese.

Site 3256V-38: Residence and Vacant Land, 11120 Tuscany Court and 12700 block of Main Street, Lemont, Cook County

- Station 159+75 to Station 161+10 (CL Main Street), 0 to 70 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(2). Contaminants of concern sampling parameters: Lead, and Manganese.
- Station 161+10 to Station 165+30 (CL Main Street), 0 to 80 feet RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance with Article 669.05(a)(5). Contaminants of concern sampling parameters: Arsenic, and Manganese.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites:

None