


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOCATION					
				SN-021	SN-031	SN-032	SN-033	SN-034	SN-039
				2C101U020L024.8	2S101I039R138.8	2S101I039R139.4	2S101I039R139.8	2S101U20BR021.5	2S071I039L118.7
25000300	SEEDING, CLASS 3	ACRE	0.75	0.10	0.13	0.13	0.13	0.13	0.13
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68	10.5	11.5	11.5	11.5	11.5	11.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68	10.5	11.5	11.5	11.5	11.5	11.5
25100630	EROSION CONTROL BLANKET	SQ YD	3,630	484	629	629	629	629	629
28000305	TEMPORARY DITCH CHECKS	FOOT	200	20	40	40	40	40	20
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	92.3	0	92.3	0	0	0	0
63000017	STEEL PLATE BEAM GUARDRAIL, TYPE D, 6 FOOT POSTS	FOOT	300	0	175	50	25	25	25
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	0	2	2	1	1	1
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	0	2	0	0	0	0
63200310	GUARDRAIL REMOVAL	FOOT	62.5	0	0	25	12.5	12.5	12.5
67100100	MOBILIZATION	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	10	0	3	3	0	2	2
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6	2	0	0	2	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	0.17	0.17	0.17	0.17	0.17	0.17
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	13,000	0	3,900	3,900	0	2,600	2,600
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,334	0	1,300	1,300	0	867	867
72000200	SIGN PANEL - TYPE 2	SQ FT	45	0	15	15	15	0	0
72000300	SIGN PANEL - TYPE 3	SQ FT	2,690	270	480	505	505	390	540
73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4' -6" X 5' -3")	FOOT	484	0	112	123	0	119	130
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5' -0" X 7' -0")	FOOT	140	0	0	0	140	0	0
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	288.25	26.5	39	39	60.25	63.25	60.25
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7' -0")	FOOT	40	40	0	0	0	0	0
73400100	CONCRETE FOUNDATIONS	CU YD	149.6	0	36.7	38.1	0	35.8	39.0
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	38.3	12.3	26	0	0	0	0
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	5	0	1	1	1	1	1
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1	0	0	0	0	0
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	11	1	2	2	2	2	2
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,300	0	325	325	0	325	325
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	132	0	33	33	0	33	33
78200410	GUARDRAIL MARKERS, TYPE A	EACH	32	8	8	4	4	4	4
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	0	2	0	0	0	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	436	0	109	109	0	109	109
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	132	0	33	33	0	33	33
X0325265	REMOVE ELECTRIC SERVICE	EACH	6	1	1	1	1	1	1

N:\PRD\1\0220080_00_0020080_01\Design\Hasc-Sheets\0220080_00_schelet01.dgn

 ENGINEERING CONSULTANT USER NAME = jattanaseo DESIGNED - JPA DRAWN - JPA CHECKED - MJL DATE - 1/31/2014 REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SIGN STRUCTURE REPLACEMENT SCHEDULE OF QUANTITIES		F.A.I. RTE. VAR.	SECTION •	COUNTY **	TOTAL SHEETS 45	SHEET NO. 6
	PLOT SCALE = 100.0000' / 1"		SCALE: N.T.S.		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.		CONTRACT NO. 46288 ILLINOIS FED. AID PROJECT