

90% FED.  
10% STATE

TRAFFIC SIGNALS 0021	63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT	LIGHTING 0021	BRIDGE 00M	ROADWAY 0004	TOTAL QUANTITY	UNIT	PAY ITEM DESCRIPTION	CODE NO.	LIRBAN
				140			140	FOOT	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	* 81100605	
			3,010		320		3,330	FOOT	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL (CDOT)	* X0370124	
				952			952	FOOT	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	* 81100805	
				102			102	FOOT	UNIT DUCT, 600 V, 3-1/C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	* 81603081	
					720		720	FOOT	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL (CDOT)	* X0370203	
				2,786			2,786	FOOT	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	* 81702110	
				932			932	FOOT	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	* 81702140	
				2,500	290		2,790	FOOT	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	* 81702150	
					870		870	FOOT	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4/0	* 81702190	
				1			1	L SUM	REMOVE EXISTING STREET LIGHTING EQUIPMENT (CDOT)	* X0370140	
					2320		2320	FOOT	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 500 MCM	* 81702230	
				1			1	EACH	RACK, SECONDARY-AERIAL, 2-WIRE (CDOT)	* X0370120	
				2,083	320		2,403	FOOT	REMOVE CONDUIT ATTACHED TO STRUCTURE	* X0323710	
				1			1	L SUM	MAINTENANCE OF STREET LIGHTING SYSTEM (CDOT)	* X0370132	
				2,692			2,692	FOOT	ELECTRIC CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND (CDOT)	* X0370003	
				1			1	EACH	PAINT EXISTING STREET LIGHT/TRAFFIC EQUIPMENT COMPLETE (CDOT)	* X0370133	
					1		2	EACH	JUNCTION BOX, POLE OR POST MOUNTED (CDOT)	* X0370134	
				30			30	EACH	REMOVE EXISTING JUNCTION BOX	* X8130125	
				1			1	L SUM	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	* X8210305	
							197	FOOT	ELECTRIC CABLE IN CONDUIT, COAXIAL VIDEO, RG-59/U (CDOT)	* X0370138	
				6			6	CAL MO	MAINTENANCE OF LIGHTING SYSTEM	* Z0033020	
							28	EACH	DRILL MANHOLE OR HANDHOLE (CDOT)	* X0370084	
							8	EACH	CLEAN MANHOLE OR HANDHOLE (CDOT)	* X0370085	
							456	FOOT	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM (CDOT)	* X0370076	
							6	EACH	BREAKDOWN STREET LIGHT FOUNDATION (CDOT)	* X0370002	
			235				316	FOOT	TRENCH AND BACKFILL WITH SCREENINGS (CDOT)	* X0370001	
							1	EACH	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/4" ANCHOR RODS, 17 1/4" BOLT CIRCLE, 9 FEET (CDOT)	* X0370086	

© 100% STATE (NP) \* Specialty Items

Rev. 6-4-14

Rev.

I:\projects\2014\20140222\CAD\1511re\vdgn\00\0160015-Summary.rxdgn  
 2/23/2014 3:24:45 AM

**GRAF**  
 8501 E. Higgins Road, Suite 200  
 Chicago, Illinois 60631  
 (773) 399-0112

USER NAME = 0766	DESIGNED - JSO	REVISIONS -
PLOT SCALE = 100.0000 1" = 100'	DRAWN - HJM	REVISIONS -
PLOT DATE = 2/31/2014	CHECKED - TNS	REVISIONS -
	DATE - 03-15-2013	REVISIONS -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**63rd STREET BRIDGE REPLACEMENT - COOK COUNTY**  
**SUMMARY OF QUANTITIES**

SCALE: NTS=0' SHEET 6 OF 8 SHEETS STA. TO STA.

F.A.I. RTE. 94	SECTION 1920-B	COUNTY COOK	TOTAL SHEETS 142	SHEET NO. 10
CONTRACT NO. 60J15			ILLINOIS FED. AID PROJECT	