


90% FED.  
10% STATE  
URBAN

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0014	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
50300225	CONCRETE STRUCTURES	CU YD	385.7		385.7				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1142.5		1142.5				
50300260	BRIDGE DECK GROOVING	SQ YD	2,390		2,390				
50300300	PROTECTIVE COAT	SQ YD	3,607		3,607				
50500105	FURNISHING & ERECTING STRUCTURAL STEEL	L SUM	1		1				
50500505	STUD SHEAR CONNECTORS	EACH	16,830		16,830				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	333,360		333,360				
50800515	BAR SPLICERS	EACH	1612		1612				
50901730	BRIDGE FENCE RAILING	FOOT	755		755				
51300105	TEMPORARY BRIDGE COMPLETE	EACH	1		1				
51500100	NAME PLATES	EACH	2		2				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	167		167				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	22		22				
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	22		22				
52100510	ANCHOR BOLTS, 3/4"	EACH	44		44				
52100520	ANCHOR BOLTS, 1"	EACH	88		88				
58700300	CONCRETE SEALER	SQ FT	8,540		8,540				
59000200	EPOXY CRACK INJECTION	FOOT	19		19				
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	9	9					
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1					
"	60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	1	1				
"	60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	1	1				
	60500050	REMOVING CATCH BASINS	EACH	4	4				
	63700805	CONCRETE BARRIER TRANSITION	FOOT	15	15				

I:\Jobs\2014\20140302\CAD\Site\Adgn\00\0160J15-Summary.dgn  
 3/31/2014 9:22:54 AM

 #501 E. Higgins Road Suite 280 Chicago, Illinois 60631 (773) 399-0112	USER NAME = 0766	DESIGNED - JSO	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>63rd STREET BRIDGE REPLACEMENT - COOK COUNTY</b> <b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100,0000' / in.	CHECKED - TNS	REVISED -					94	1920-B	COOK	142	6
PLOT DATE = 3/31/2014	DATE - 03-15-2013	REVISED -	SCALE: NTP80'		SHEET 2	OF 8	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60J15		