


90% FED.
10% STATE
URBAN

CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0004	LIGHTING 0021	TRAFFIC SIGNALS 0021		
							63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
X2011000	TEMPORARY FENCE (SPECIAL)	FOOT	453		453				
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POLYND	97	97					
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	92		92				
X6020083	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1					
X6022505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	4	4					
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	235	235					
Z0004552	APPROACH SLAB REMOVAL	SO YD	738	738					
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	797		797				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	4		4				
Z0018800	DRAINAGE SYSTEM	L SUM	1		1				
Z0026407	TEMPORARY SHEET PILING	SO FT	327		327				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0073100	TEMPORARY SHORING	EACH	4		4				
X0370135	CONCRETE CURB, TYPE B SPECIAL (CDOT)	FOOT	101	101					
X0370080	COMBINATION CURB AND GUTTER TYPE B V.12 (CDOT)	FOOT	400	400					
31101860	SUBBASE GRANULAR MATERIAL, TYPE B 24"	SO YD	43	43					
X0327617	MODIFY CONCRETE BARRIER AND RETAINING WALL	L SUM	1	1					
X0370081	SAND CUSHION, 4" (CDOT)	SO FT	2,538	2,538					
X0327618	LANDSCAPING, SPECIAL	L SUM	1	1					
X0370082	STORM SEWER, TYPE 2, 8 INCH, EXTRA STRENGTH VITRIFIED CLAY PIPE (CDOT)	FOOT	98	98					
X0370083	STORM SEWER, TYPE 2, 8 INCH, DUCTILE IRON PIPE (CDOT)	FOOT	113	113					
* X0370121	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL (CDOT)	FOOT	518			518			
* X0370122	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL (CDOT)	FOOT	634			634			

*specialty items

Rev.

 <p>8521 W. Higgins Road Suite 200 Chicago, Illinois 60634 (773) 399-0122</p>	USER NAME = 0765	DESIGNED - JSO	REVISED -	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES</p>			F.A.I. RTE. 94	SECTION 1920-B	COUNTY COOK	TOTAL SHEETS 142	SHEET NO. 9
	PLOT SCALE = 100.0000' / 1"	CHECKED - TNS	REVISED -		SCALE: NTS=0'	SHEET 5	OF 8 SHEETS	STA. TO STA.	CONTRACT NO. 60J15		ILLINOIS FED. AID PROJECT	
	PLOT DATE = 3/31/2014	DATE - 03-15-2013	REVISED -									

H:\Jobs\2014\20140322\CAD\Site\Drawings\00\0160J15-Summary.dgn
 03/31/2014 10:42:38 AM