


90% FED,  
10% STATE

	CODE NO.	PAY ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ROADWAY 0004	BRIDGE 0014	LIGHTING 0021	TRAFFIC SIGNALS 0021		
								63RD ST/ YALE AVE	63RD ST/ WENTWORTH AVE	INTER-CONNECT
"	* X0370108	INNERDUCT IN CONDUIT, 1 1/4" (CDOT)	FOOT	532						532
"	* X0370109	FIBER OPTIC HYBRID CABLE IN CONDUIT 6SM/6MM (CDOT)	FOOT	680						680
"	* X0370110	CABINET WORK, SPLICING, TESTING AND MISC. (CDOT)	EACH	2				1	1	
"	* X0370111	GALVANIZED STEEL CONDUIT IN TRENCH, 3-INCH DIA. (CDOT)	FOOT	1,178						1,178
"	* X0370112	PVC CONDUIT IN TRENCH, 3-INCH DIA. (CDOT)	FOOT	162				84	78	
"	* X0370113	TRACER CABLE (CDOT)	FOOT	532						532
"	* X0370114	RACKING CABLES IN MANHOLE OR HANDHOLE (CDOT)	EACH	8				4	4	
"	* X0370115	POLE, STEEL, 32'6", ANCHOR BASE, 1 1/2" DIAMETER BOLT CIRCLE, 7 GAUGE, (INSTALL ONLY) (CDOT)	EACH	4			4			
"	* X0370116	MAST ARM, STEEL, STREET LIGHTING, 8 FOOT (INSTALL ONLY) (CDOT)	EACH	9			9			
"	* X0370117	MAST ARM, STEEL, STREET LIGHTING, 15 FOOT (INSTALL ONLY) (CDOT)	EACH	4			4			
"	* X0370118	LUMINAIRE, STREET LIGHT, CERAMIC METAL HALIDE, 210 WATT, 240 VOLT, ARTERIAL, SEMI-CUTOFF (INSTALL ONLY) (CDOT)	EACH	15			15			
∅	Z0076600	TRAINEES	HOUR	1000	1000					
"	* X0370119	WIRE, AERIAL, 1/C NO. 6 (CDOT)	FOOT	260			260			
∅	Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	1000	1000					

- \* DENOTES SPECIALTY ITEM
- DENOTES CHICAGO DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION
- ∅ 0042

H:\10042014\20140227\CAD\5178\5178.dgn\00\0160\05 - Summary.rvt

 9501 W. Higgins Road, Suite 280 Chicago, Illinois 60631 (773) 399-0112	USER NAME - 0756	DESIGNED - JSO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	63rd STREET BRIDGE REPLACEMENT - COOK COUNTY SUMMARY OF QUANTITIES			F.A.I. RATE - 94	SECTION - 1920-B	COUNTY - COOK	TOTAL SHEETS - 142	SHEET NO. - 12			
	PLOT SCALE - 100.0000' / 1" =	CHECKED - TNS	REVISED -					SCALE: NTS/50'	SHEET 8	OF 8 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE - 3/21/2014	DATE - 03-15-2013	REVISED -					CONTRACT NO. 60J15							