


CONSTRUCTION CODE
ROADWAY 0003
80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	43	43
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	89	89
20200100	EARTH EXCAVATION	CU YD	9,745	9,745
+ 20200200	ROCK EXCAVATION	CU YD	495	495
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,865	2,865
20800150	TRENCH BACKFILL	CU YD	22	22
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3,785	3,785
25000210	SEEDING, CLASS 2A	ACRE	3.25	3.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	329	329
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	329	329
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	329	329
⊙ 25000750	MOWING	ACRE	3	3
25100135	MULCH, METHOD 4	ACRE	3.25	3.25
25100630	EROSION CONTROL BLANKET	SQ YD	17,693	17,693

+ SPECIALTY ITEM
⊙ 100% STATE (NP)

FILE NAME = S:\JUL16200--S39916346\043\Micro\Load Sheets\0160P51-int-500.dgn



1170 SOUTH HOBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennis
MODEL NAME = Default
PLOT SCALE = 2,000' / 1" =
PLOT DATE = 2/18/2014

DESIGNED - MAG
DRAWN - JKP/DJW
CHECKED - BMA
DATE - 12-5-12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 1 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-IAC-2	WILL	102	4
CONTRACT NO. 60P51			ILLINOIS FED. AID PROJECT	