


CONSTRUCTION CODE	
ROADWAY	0003
80% FED.	20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	340	340
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5,402	5,402
28000305	TEMPORARY DITCH CHECKS	FOOT	190	190
28000400	PERIMETER EROSION BARRIER	FOOT	2,880	2,880
28000500	INLET AND PIPE PROTECTION	EACH	11	11
28000510	INLET FILTERS	EACH	14	14
28001000	AGGREGATE (EROSION CONTROL)	TON	57	57
28100105	STONE RIPRAP, CLASS A3	SO YD	35	35
28100107	STONE RIPRAP, CLASS A4	SO YD	52	52
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	44	44
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SO YD	417	417
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	7,661	7,661
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	324	324
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	5,229	5,229

+ SPECIALTY ITEM

FILE NAME = S:\JULI6380-6099\6345\645\Micro\CA00 Sheet\0165P51-INT-500.dgn



USER NAME	= dennisw
MODEL NAME	= Default
PLOT SCALE	= 2.0000 1" = 10'
PLOT DATE	= 3/31/2014

DESIGNED	= MAG	REVISED	=
DRAWN	= JKP/DJW	REVISED	=
CHECKED	= BMA	REVISED	=
DATE	= 12-5-12	REVISED	=

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A SHEET 2 OF 7 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-IAC-2	WILL	102	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60P51	