



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 4, 2014

SUBJECT: FAU Route 3565 (IL 171)
Project ACHSIP-3565(006)
Section B-N-5
Cook County
Contract No. 60T24
Item No. 221, June 13, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised sheets 7, 8, 26, 43, 44, 46, 47, 48, 75 & 86 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; D. Carl Puzey; Estimates

MS/kf

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60T24

State Job # - C-91-312-12

County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2001716	T-ACER SACR 2	EACH	4.000				
B2000766	T-AMEL X GF AB SF 6'	EACH	2.000				
D2002984	E-PINUS STROBUS 7'	EACH	6.000				
K0029634	WEED CONTR PRE-EM GRN	POUND	12.000				
X0324455	DRILL/SET SOLD P SOIL	CU FT	10,928.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	2.000				
X4022000	TEMP ACCESS- COM ENT	EACH	4.000				
X4060110	BIT MATLS PR CT	POUND	9,251.000				
X4400100	PCC SURF REM VAR DP	SQ YD	1,300.000				
X5537800	SS CLEANED 12	FOOT	400.000				
X5860110	GRANULAR BACKFILL STR	CU YD	370.000				
X6020094	MAN TA 6D T1F CL R-P	EACH	2.000				
X6030310	FR & LIDS ADJUST SPL	EACH	20.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7030025	WET REF TEM TP T3 L&S	SQ FT	1,080.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -

Code - 31 - -

District - 1 - -

Section Number - B-N-5

Project Number

ACHSIP-3565/006/

*REVISED: JUNE 03, 2014

Route

FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7030030	WET REF TEM TAPE T3 4	FOOT	4,290.000				
X7030040	WET REF TEM TAPE T3 6	FOOT	1,350.000				
X7030050	WET REF TEM TPE T3 12	FOOT	285.000				
X7030055	WET REF TEM TPE T3 24	FOOT	240.000				
X8570226	FAC T4 CAB SPL	EACH	1.000				
X8620200	UNINTER POWER SUP SPL	EACH	1.000				
X8730250	ELCBL C 20 3C TW SH	FOOT	803.000				
Z0006016	BR DK LTX C OLY 2 3/4	SQ YD	290.000				
Z0007118	UNTREATED TIMBER LAG	SQ FT	2,743.000				
Z0012146	BR DECK SCAR 2 3/4	SQ YD	290.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	13.000				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	10.000				
Z0026404	FUR SOLDIER PILES WS	FOOT	1,623.000				
Z0026407	TEMP SHT PILING	SQ FT	400.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030850	TEMP INFO SIGNING	SQ FT	102.800				
Z0046304	P UNDR FOR STRUCT 4	FOOT	293.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	1.000				
Z0076600	TRAINEES	HOUR	1,000.000		0.800		800.000
Z0076604	TRAINEES TPG	HOUR	1,000.000		10.000		10,000.000
20100110	TREE REMOV 6-15	UNIT	21.000				
20100210	TREE REMOV OVER 15	UNIT	60.000				
20101000	TEMPORARY FENCE	FOOT	1,971.000				
20101100	TREE TRUNK PROTECTION	EACH	2.000				
20101200	TREE ROOT PRUNING	EACH	4.000				
20101350	TREE PRUN OVER 10	EACH	10.000				
20200100	EARTH EXCAVATION	CU YD	50.000				
20400800	FURNISHED EXCAVATION	CU YD	3,490.000				
20800150	TRENCH BACKFILL	CU YD	920.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
21101505	TOPSOIL EXC & PLAC	CU YD	3,272.000				
25000400	NITROGEN FERT NUTR	POUND	72.000				
25000500	PHOSPHORUS FERT NUTR	POUND	72.000				
25000600	POTASSIUM FERT NUTR	POUND	72.000				
25100135	MULCH METHOD 4	ACRE	0.800				
25200110	SODDING SALT TOLERANT	SQ YD	3,865.000				
25200200	SUPPLE WATERING	UNIT	45.000				
28000250	TEMP EROS CONTR SEED	POUND	81.000				
28000305	TEMP DITCH CHECKS	FOOT	84.000				
28000400	PERIMETER EROS BAR	FOOT	1,760.000				
28000510	INLET FILTERS	EACH	43.000				
30300001	AGG SUBGRADE IMPROVE	CU YD	141.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	1,763.000				
35101800	AGG BASE CSE B 6	SQ YD	1,673.000				
35300500	PCC BSE CSE 10	SQ YD	993.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
35501316	HMA BASE CSE 8	SQ YD	670.000				
40600400	MIX CR JTS FLANGEWYS	TON	3.000				
40600827	P LB MM IL-4.75 N50	TON	528.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	198.000				
40601005	HMA REPL OVER PATCH	TON	16.000				
40603335	HMA SC "D" N50	TON	357.000				
40603595	P HMA SC "F" N90	TON	1,454.000				
42001300	PROTECTIVE COAT	SQ YD	2,364.000				
42400200	PC CONC SIDEWALK 5	SQ FT	5,107.000				
42400800	DETECTABLE WARNINGS	SQ FT	200.000				
44000100	PAVEMENT REM	SQ YD	103.000				
44000159	HMA SURF REM 2 1/2	SQ YD	1,849.000				
44000500	COMB CURB GUTTER REM	FOOT	2,264.000				
44000600	SIDEWALK REM	SQ FT	6,857.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60T24

State Job # - C-91-312-12

County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44002210	HMA RM OV PATCH 2 1/2	SQ YD	110.000				
44201765	CL D PATCH T2 10	SQ YD	205.000				
44201769	CL D PATCH T3 10	SQ YD	25.000				
44201771	CL D PATCH T4 10	SQ YD	185.000				
48102100	AGG WEDGE SHLD TYPE B	TON	5.000				
50102400	CONC REM	CU YD	38.500				
50157300	PROTECTIVE SHIELD	SQ YD	2,320.000				
50200100	STRUCTURE EXCAVATION	CU YD	80.000				
50300225	CONC STRUCT	CU YD	145.000				
50300255	CONC SUP-STR	CU YD	33.000				
50300260	BR DECK GROOVING	SQ YD	268.000				
50300285	FORM LINER TEX SURF	SQ FT	3,166.000				
50300300	PROTECTIVE COAT	SQ YD	469.000				
50500505	STUD SHEAR CONNECTORS	EACH	438.000				
50800205	REINF BARS, EPOXY CTD	POUND	16,130.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0340	STORM SEW CL A 2 12	FOOT	478.000				
550A0360	STORM SEW CL A 2 15	FOOT	139.000				
*REV 550A0380	STORM SEW CL A 2 18	FOOT	310.000				
550A0410	STORM SEW CL A 2 24	FOOT	575.000				
550A0640	STORM SEW CL A 3 12	FOOT	30.000				
*ADD 550A0680	STORM SEW CL A 3 18	FOOT	44.000				
*REV 550A0710	STORM SEW CL A 3 24	FOOT	123.000				
550A4100	SS CL A 1 EQRS 24	FOOT	147.000				
*REV 55100500	STORM SEWER REM 12	FOOT	1,236.000				
*REV 55100700	STORM SEWER REM 15	FOOT	216.000				
*ADD 55100900	STORM SEWER REM 18	FOOT	16.000				
55101200	STORM SEWER REM 24	FOOT	378.000				
58700300	CONCRETE SEALER	SQ FT	3,098.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	220.000				
60107600	PIPE UNDERDRAINS 4	FOOT	650.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60108100	PIPE UNDERDRAIN 4 SP	FOOT	35.000				
*DEL 60200105	CB TA 4 DIA T1F OL	EACH	1.000				
*ADD 60200805	CB TA 4 DIA T8G	EACH	1.000				
60201340	CB TA 4 DIA T24F&G	EACH	21.000				
60203805	CB TA 5 DIA T1F OL	EACH	1.000				
60204505	CB TA 5 DIA T8G	EACH	1.000				
60205040	CB TA 5 DIA T24F&G	EACH	1.000				
60218400	MAN TA 4 DIA T1F CL	EACH	4.000				
*REV 60221100	MAN TA 5 DIA T1F CL	EACH	15.000				
60255410	CB CLEANED	EACH	27.000				
60257900	MAN RECONST	EACH	1.000				
60300305	FR & LIDS ADJUST	EACH	10.000				
60406000	FR & LIDS T1 OL	EACH	1.000				
*ADD 60500040	REMOV MANHOLES	EACH	15.000				
60500050	REMOV CATCH BAS	EACH	5.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*REV 60500060	REMOV INLETS	EACH	22.000				
60602800	CONC GUTTER TB	FOOT	267.000				
60603800	COMB CC&G TB6.12	FOOT	468.000				
60605000	COMB CC&G TB6.24	FOOT	2,109.000				
60618740	CONC MED TM2.12	SQ FT	2,387.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	297.000				
63100045	TRAF BAR TERM T2	EACH	1.000				
63100085	TRAF BAR TERM T6	EACH	1.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	1.000				
63200310	GUARDRAIL REMOV	FOOT	297.000				
66900200	NON SPL WASTE DISPOSL	CU YD	1,850.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	10.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70106800	CHANGEABLE MESSAGE SN	CAL MO	3.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	583.000				
70300220	TEMP PVT MK LINE 4	FOOT	7,235.000				
70300240	TEMP PVT MK LINE 6	FOOT	3,126.000				
70300250	TEMP PVT MK LINE 8	FOOT	82.000				
70300260	TEMP PVT MK LINE 12	FOOT	471.000				
70300280	TEMP PVT MK LINE 24	FOOT	262.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	825.000				
72000100	SIGN PANEL T1	SQ FT	15.000				
72000200	SIGN PANEL T2	SQ FT	65.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	583.000				
78000200	THPL PVT MK LINE 4	FOOT	7,235.000				
78000400	THPL PVT MK LINE 6	FOOT	3,126.000				
78000500	THPL PVT MK LINE 8	FOOT	82.000				
78000600	THPL PVT MK LINE 12	FOOT	471.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78000650	THPL PVT MK LINE 24	FOOT	262.000				
78008230	POLYUREA PM T1 LN 6	FOOT	150.000				
78100100	RAISED REFL PAVT MKR	EACH	153.000				
78200410	GUARDRAIL MKR TYPE A	EACH	4.000				
78201000	TERMINAL MARKER - DA	EACH	1.000				
78300200	RAISED REF PVT MK REM	EACH	130.000				
80500010	SERV INSTALL GRND MT	EACH	1.000				
81028200	UNDRGRD C GALVS 2	FOOT	886.000				
81028220	UNDRGRD C GALVS 3	FOOT	24.000				
81028240	UNDRGRD C GALVS 4	FOOT	513.000				
81400100	HANDHOLE	EACH	4.000				
81400200	HD HANDHOLE	EACH	4.000				
81400300	DBL HANDHOLE	EACH	2.000				
85000200	MAIN EX TR SIG INSTAL	EACH	1.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	1,344.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60T24

State Job # - C-91-312-12

County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - B-N-5

Project Number
 ACHSIP-3565/006/
 *REVISED: JUNE 03, 2014

Route
 FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301225	ELCBL C SIGNAL 14 3C	FOOT	2,313.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	2,605.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	1,663.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	2,000.000				
87301805	ELCBL C SERV 6 2C	FOOT	160.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	600.000				
87502500	TS POST GALVS 16	EACH	2.000				
87700240	S MAA & P 40	EACH	1.000				
87700270	S MAA & P 46	EACH	1.000				
87702574	S MAA & P DMA 36 & 54	EACH	1.000				
87702719	STL MAAAP DMA 46 & 34	EACH	1.000				
87800100	CONC FDN TY A	FOOT	8.000				
87800150	CONC FDN TY C	FOOT	4.000				
87800415	CONC FDN TY E 36D	FOOT	26.000				
87800420	CONC FDN TY E 42D	FOOT	42.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60T24

State Job # - C-91-312-12

Project Number

Route

County Name - COOK - -

ACHSIP-3565/006/

FAU 3565

Code - 31 - -

*REVISED: JUNE 03, 2014

District - 1 - -

Section Number - B-N-5

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88030020	SH LED 1F 3S MAM	EACH	10.000				
88030110	SH LED 1F 5S MAM	EACH	5.000				
88030220	SH LED 2F 5S BM	EACH	1.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	1.000				
88102717	PED SH LED 1F BM CDT	EACH	4.000				
88102747	PED SH LED 2F BM CDT	EACH	2.000				
88200100	TS BACKPLATE	EACH	15.000				
88500100	INDUCTIVE LOOP DETECT	EACH	10.000				
88600100	DET LOOP T1	FOOT	1,036.000				
88700200	LIGHT DETECTOR	EACH	3.000				
88700300	LIGHT DETECTOR AMP	EACH	1.000				
88800100	PED PUSH-BUTTON	EACH	8.000				
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89502375	REMOV EX TS EQUIP	EACH	1.000				
89502380	REMOV EX HANDHOLE	EACH	7.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60T24

State Job # - C-91-312-12

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - B-N-5

Project Number

ACHSIP-3565/006/

*REVISED: JUNE 03, 2014

Route

FAU 3565

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89502382	REMOV EX DBL HANDHOLE	EACH	1.000				
89502385	REMOV EX CONC FDN	EACH	9.000				