

90% FED,  
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				STP ACB	NHPP ACNHPP	NHPP ACNHPP			
				ROADWAY	BRIDGE	BRIDGE			
				0004	0014	0014			
				RURAL	S. N. 099-0181	S. N. 099-0182			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	30	30					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	322	322					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	129	129					
40701826	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 7 1/4"	SQ YD	1043	1043					
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	2094	2094					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	66	66					
44000100	PAVEMENT REMOVAL	SQ YD	5915	5915					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	692	692					
44000400	GUTTER REMOVAL	FOOT	1242	1242					
44004000	PAVED DITCH REMOVAL	FOOT	110	110					
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	40	40					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	40	40					
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	40	40					
48101202	AGGREGATE SHOULDERS, TYPE B	CU YD	406	406					

FILE NAME: F:\3-1319\_Bldg\319\_Bldg\319\_CAD\319\_Sht3.dwg



USER NAME = jborger	DESIGNED - MMO	REVISED -
PLOT SCALE = 2,000' / 1" =	DRAWN - BL	REVISED -
PLOT DATE = 3/31/2014	CHECKED - LSA	REVISED -
	DATE - 12/4/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET 3	OF 9 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-31-3	WILL	87	5
			CONTRACT NO. 60X60	
ILLINOIS FED. AID PROJECT				