


90% FED.
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				STP ACE ROADWAY 0004 RURAL	NHPP ACNHPP BRIDGE 0014 S. N. 099-0181	NHPP ACNHPP BRIDGE 0014 S. N. 099-0182			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5280		5280				
50500505	STUD SHEAR CONNECTORS	EACH	1890		1890				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	57020		57020				
50901050	STEEL RAILING, TYPE SM	FOOT	272		272				
51500100	NAME PLATES	EACH	1		1				
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	21		21				
52100505	ANCHOR BOLTS, 5/8"	EACH	14		14				
52100520	ANCHOR BOLTS, 1"	EACH	28		28				
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	192	192					
54215547	METAL END SECTIONS 12"	EACH	3	3					
54246205	INLET BOX, STANDARD 542526	EACH	1	1					
54261624	CONCRETE END SECTION, STANDARD 542001, 24", 1:6	EACH	3	3					
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	62		62				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	8	4	4				

14

FILE NAME: F:\3-131\Bldg\14\Bldg\14\Drawings\CADD\Sheet\0160936.pht-500.dwg



USER NAME = sberges	DESIGNED - MMO	REVISED -
PLOT SCALE = 2,000' / 1" =	DRAWN - BL	REVISED -
PLOT DATE = 3/31/2014	CHECKED - LSA	REVISED -
	DATE - 12/4/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET 5 OF 9 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-31-3	WILL	87	7
			CONTRACT NO. 60X60	
ILLINOIS FED. AID PROJECT				