

REMOVALS

	44000100	44000158	44000400	44004000	Z0022800
	PAVEMENT REMOVAL (SQ. YD.)	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" (SQ. YD.)	GUTTER REMOVAL (FOOT)	PAVED DITCH REMOVAL (FOOT)	FENCE REMOVAL (FOOT)
STATION TO STATION					
EAST FRONTAGE RD 1429+76 1431+07		692			
WEST FRONTAGE RD 1424+61 1431+22	2422		491	110	
BLODGETT RD 42+24 45+54	702		54		
45+00 45+53.54			293		
45+53.54 48+45.83	682		404		
50+96 55+00	922				
55+00 57+07	501				
58+11 59+80	397				
EX. EMERGENCY ACCESS	289				
RAMP C ACCESS					75
TOTAL	5915	692	1242	110	75

PAVEMENT MARKING

	63500105 DELINEATORS (EACH)	78000200 THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	78201000 TERMINAL MARKER DIRECT APPLIED (EACH)
BLODGETT RD & W FRONTAGE RD WEST OF 55			
56+62.43 TO 59+80.00	8	1271	2
148+80.00 TO 156+62.43	18	3130	2
BLODGETT RD & E FRONTAGE RD EAST OF 55			
1429+76.00 TO 1431+17.00		564	
42+24.13 TO 43+80.00		624	
TOTAL	26	5589	4


CONTINGENCY ITEMS

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	20200200 ROCK EXCAVATION (CU YD)	20700220 POROUS GRANULAR EMBANKMENT (CU YD)	40201000 AGGREGATE FOR TEMPORARY ACCESS (TON)	44201773 CLASS D PATCHES, TYPE I, 11 INCH (SQ YD)	44201777 CLASS D PATCHES TYPE II, 11 INCH (SQ YD)	44201781 CLASS D PATCHES, TYPE III, 11 INCH (SQ YD)	50200400 ROCK EXCAVATION FOR STRUCTURES (CU YD)
200	10	200	20	40	40	40	3

PAVING

STATION TO STATION	30300112 AGGREGATE SUBGRADE IMPROVEMENT 12" (SQ YD)	31102000 SUBBASE GRANULAR MATERIAL, TYPE C (CU YD)	X4060110 BITUMINOUS MATERIALS (PRIME COAT) (POUND)	40600635 LEVELING BINDER (MACHINE METHOD) N70 (TON)	40603085 HOT-MIX ASPHALT BINDER COURSE IL-19.0, N70 (TON)	40603340 HOT-MIX ASPHALT SURFACE COURSE MIX "D", N70 (TON)	40701826 HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 7 1/4" (SQ YD)	40701941 HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 13" (SQ YD)	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) (SQ YD)	48101202 AGGREGATE SHOULDERS, TYPE B (CU YD)	48203026 HOT-MIX ASPHALT SHOULDERS 7 1/4" (SQ YD)	48203029 HOT-MIX ASPHALT SHOULDERS 8" (SQ YD)	60602800 CONCRETE GUTTER, TYPE B (FOOT)	66101150 HOT-MIX ASPHALT SHOULDER CURB (FOOT)
EAST FRONTAGE RD 1429+76.00 1431+07.40			468	30		59								
BLODGETT RD 42+24.13 45+53.54	1106		1980				733			37	228			
WEST FRONTAGE RD / BLODGETT CONNECTOR														
148+80.00 149+90.88	407	8	904					309		17			111	
149+90.88 155+10.14	1962	73	4052					1385		154			462	
155+10.14 155+60.14	184	7	375					128		15			45	
156+60.14 156+62.43	364	15	735					251		31			91	
BLODGETT RD 56+62.43 56+70.83	31	2	62					21		2			8	
56+70.83 56+77.30	24		65						22	2				
58+40.45 58+53.59	48		119						44	4				27
58+53.59 59+80.00	453		837				310			30	113			30
EX. EMERGENCY ACCESS	263		711		118	30				57				
RAMP C EMERGENCY ACCESS	357		964		160	40				57				
EX. MEDIAN CROSS-OVER			317		44									
TOTALS	5199	105	11589	30	322	129	1043	2094	66	406	341	656	111	57

FILE NAME = F:\3-1319-Blodgett\Drawings\CADD\Sheets\0160636-shr-schedule.dgn



USER NAME = tborges	DESIGNED - MMO	REVISED -
	DRAWN - PDF	REVISED -
PLOT SCALE = 2.0000' / 1" =	CHECKED - LSA	REVISED -
PLOT DATE = 3/31/2014	DATE - 12/4/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET 1 OF 4 SHEETS STA. TO STA.

F.A.I. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-31-3	WILL	87	12
CONTRACT NO. 60X60			ILLINOIS FED. AID PROJECT	