

**EROSION AND SEDIMENT CONTROL & LANDSCAPING**

	PERMANENT											TEMPORARY							
	21101505 TOPSOIL EXCAVATION AND PLACEMENT (CU YD)	25000210 SEEDING CLASS 2A (ACRE)	25000310 SEEDING CLASS 4 (ACRE)	25000400 NITROGEN FERTILIZER NUTRIENT (POUND)	25000500 PHOSPHORUS FERTILIZER NUTRIENT (POUND)	25000600 POTASSIUM FERTILIZER NUTRIENT (POUND)	25100115 MULCH METHOD 2 (ACRE)	25100635 HEAVY DUTY EROSION CONTROL BLANKET (SQ YD)	25100900 TURF REINFORCE- MENT MAT (SQ YD)	28100105 STONE RIPRAP, CLASS A3 (SQ YD)	28100109 STONE RIPRAP, CLASS A5 (SQ YD)	20101000 TEMPORARY FENCE (FOOT)	25100115 MULCH METHOD 2 (ACRE)	28000250 TEMPORARY EROSION CONTROL SEEDING (POUND)	28000305 TEMPORARY DITCH CHECK (FOOT)	28000400 PERIMETER EROSION BARRIER (FOOT)	28000500 INLET AND PIPE PROTECTION (EACH)	28001200 TEMP. HEAVY DUTY EROSION CONTROL BLANKET (SQ YD)	XX006223 PERIMETER EROSION BARRIER - MODIFIED (FOOT)
E. FRONTAGE RD											320								
BLODGETT ROAD	49						0.08					0.08	8		470				
42+24.13 45+53.54	163	0.08		8	8	8	0.26				200	0.26	26		590	1			
45+53.54 48+45.83	149		0.26				0.24				250	0.24	24		400				
50+95.49 53+29			0.24																180
FAI 55 AT BRIDGE																			
EAST SIDE SLOPE	31		0.05					234			490		5		100			234	
MEDIAN	47	0.07		7	7	7	0.07					0.07	7						
WEST SIDE SLOPE	27		0.05					206			560		5		100			206	
BLODGETT ROAD																			
58+10.63 60+00	147		0.24					1124		10	600		24		70	2	1124	480	
W. FRONTAGE RD																			
148+80.00 157+07.12	816	0.15	1.14	14	14	14	0.81	2130	220		2000	0.81	129		1000	3	2130	700	
EX. EMERGENCY ACCESS	115	0.18		17	17	17		883					18	32				883	
RAMP C EMERGENCY ACCESS	74	0.12		11	11	11	0.09	127		10		0.09	12	32	275		127		
BRIDGE OVER GRANT CREEK																			
EAST SLOPE											565								
WEST SLOPE											440								
TOTALS	1617	0.60	1.98	57	57	57	1.55	4704	220	20	1005	4420	1.55	258	64	3005	6	4704	1360

\* COMPUTED BY 4" TOPSOIL  
PLACED WITHOUT REGARD  
TO WHERE EXCAVATED AND  
THEN SHRINKAGE FACTOR  
0.15 APPLIED.

FILE NAME = F:\3-1319-Blodgett\Drawings\CADD\Sheets\0160636-shr-schedule.dgn



USER NAME = makrent  
DESIGNED - MMO  
DRAWN - PDF  
PLOT SCALE = 2.0000' / in.  
PLOT DATE = 4/1/2014

REVISOR -  
REVISION -  
CHECKED - LSA  
DATE - 12/4/2013

REVISOR -  
REVISION -  
CHECKED -  
DATE -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET 4 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-2HB-31-3	WILL	87	15
CONTRACT NO. 60X60			ILLINOIS FED. AID PROJECT	