

SUMMARY OF QUANTITIES

CODE #	ITEM	UNIT	URBAN		
			TOTAL QUANTITY	ROCK ISLAND 90% FED 10% STATE 0005	WHITESIDE 90% FED 10% STATE 0005
20400800	FURNISHED EXCAVATION	CU YD	60	60	0
26100203	STONE RIPRAP, CLASS A2	TON	20	0	20
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	71	71	0
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	37	37	0
40600535	LEVELING BINDER (HAND METHOD), N70	TON	94	94	0
40600545	LEVELING BINDER (HAND METHOD), N90	TON	320	320	0
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	1,325	1,325	0
40600895	CONSTRUCTING TEST STRIP	EACH	5.0	5.0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,200	1,200	0
40600990	TEMPORARY RAMP	SQ YD	7,718	7,678	40
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	56,317	55,442	875
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	23,778	23,368	410
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,988	1,988	0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	37,612	36,981	631
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	69	69	0
44000400	GUTTER REMOVAL	FOOT	80	80	0
44000183	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	287,857	282,853	5004
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	3,483	2,920	563
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	24,466	24,466	0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	434,408	427,464	6944
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SQ YD	881	881	0
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	171	171	0
44200571	CLASS A PATCHES, TYPE IV, 11 INCH	SQ YD	1,895	1,895	0

CODE #	ITEM	UNIT	URBAN		
			TOTAL QUANTITY	ROCK ISLAND 90% FED 10% STATE 0005	WHITESIDE 90% FED 10% STATE 0005
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	555	555	0
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	36	36	0
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	711	711	0
44201299	DOWEL BARS 1 1/2"	EACH	2,640	2,640	0
44213000	PATCHING REINFORCEMENT	SQ YD	2,947	2,947	0
44213100	PAVEMENT FABRIC	SQ YD	36	36	0
44213200	SAW CUTS	FOOT	13,620	13,620	0
44213204	TIE BARS 3/4"	EACH	496	496	0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	18,686	18,373	313
50800105	REINFORCEMENT BARS	POUND	6.0	0	6
54002020	EXPANSION BOLTS 3/4 INCH	EACH	4.0	0	4
54248510	CONCRETE COLLAR	CU YD	0.3	0.0	0.3
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	650	525	125
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	0
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	8	7	1
63200310	GUARDRAIL REMOVAL	FOOT	125.0	0.0	125
63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARDRAIL	FOOT	712.5	712.5	0
63500105	DELINEATORS	EACH	35	35	0
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	349,106	343,278	5828
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST	EACH	2	2	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10	0
67100100	MOBILIZATION	L SUM	1	1	0

*SPECIALTY ITEM

FILE NAME *	USER NAME * djozan	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
D:\Projects\Rock_Island\64065-1-88-Cold	filling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line/Mar	REVISED VFWL\64065.dgn			88	(161-1) RS-1	ROCK ISLAND	104	3	
	PLOT SCALE = 1/8" = 1' / 1"	CHECKED -	REVISED -			CONTRACT NO. 64065					
Default	PLOT DATE = Wed Mar 19 10:55:25 2014	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					