

# SCHEDULE OF QUANTITIES

## 30300001 AGGREGATE SUBGRADE IMPROVEMENT

CU YD	LOCATION	REMARKS
16	MAINLINE EASTBOUND	AS DIRECTED BY RESIDENT ENGINEER
20	MAINLINE WESTBOUND	AS DIRECTED BY RESIDENT ENGINEER
22	RAMPS	AS DIRECTED BY RESIDENT ENGINEER
13	NEW PAD FOR IMPACT ATTENUATORS	AS DIRECTED BY RESIDENT ENGINEER
<b>TOTAL</b>	<b>71</b>	

## 31101000 SUBBASE GRANULAR MATERIAL, TYPE B

TON	LOCATION	REMARKS
37	STA 39+09.00 - 39+89.00 EB	NEW CONCRETE GUTTER (SPECIAL) UNDER OLD IL 2
<b>TOTAL</b>	<b>37</b>	

## 40600535 LEVELING BINDER (HAND METHOD), N70

TON	LOCATION	REMARKS
94.0	ALL RAMPS EXCEPT I-80 RAMPS	10 TON/MILE
<b>TOTAL</b>	<b>94.0</b>	

## 40600545 LEVELING BINDER (HAND METHOD), N90

TON	LOCATION	REMARKS
136.0	EASTBOUND ROCK ISLAND	10 TON/MILE
2.6	EASTBOUND WHITESIDE	10 TON/MILE
137.0	WESTBOUND ROCK ISLAND	10 TON/MILE
2.9	WESTBOUND WHITESIDE	10 TON/MILE
41.0	I-80 RAMPS	10 TON/MILE
<b>TOTAL</b>	<b>319.5</b>	

## 40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ. YD	LOCATION	REMARKS
	<i>MAINLINE EASTBOUND</i>	
200	STA 804+01.00 - 804+76.00	BEGINNING OF PROJECT
200	STA 540+15.00 - 540+90.00	3.75" - 0" TAPER SECTION
200	STA 545+02.50 - 545+77.50	3.75" - 0" TAPER SECTION
200	STA 631+29.00 - 632+04.00	3.75" - 0" TAPER SECTION
200	STA 635+66.50 - 636+41.50	3.75" - 0" TAPER SECTION
	<i>MAINLINE WESTBOUND</i>	
200	STA 804+01.00 - 804+76.00	BEGINNING OF PROJECT
<b>TOTAL</b>	<b>1200</b>	

## 40600990 TEMPORARY RAMP

SQ YD	LOCATION	REMARKS
	<i>MAINLINE EASTBOUND ROCK ISLAND CO</i>	
13.33	STA 804+51.00 - 804+56.00	5' X 24'
28.88	STA 805+01.00 - 805+11.83	10.83' X 24'
13.33	STA 195+90.00 - 195+95.00	5' X 24'
13.33	STA 196+73.00 - 196+78.00	5' X 24'
13.33	STA 477+85.00 - 477+90.00	5' X 24'
13.33	STA 478+73.00 - 478+78.00	5' X 24'
13.33	STA 540+85.00 - 540+90.00	5' X 24'
13.33	STA 543+90.00 - 543+95.00	5' X 24'
13.33	STA 631+99.00 - 632+04.00	5' X 24'
13.33	STA 634+54.00 - 634+59.00	5' X 24'
13.33	STA 710+36.00 - 710+41.00	5' X 24'
13.33	STA 712+67.00 - 712+72.00	5' X 24'

## 40600990 TEMPORARY RAMP (cont.)

SQ YD	LOCATION	REMARKS
	<i>MAINLINE WESTBOUND ROCK ISLAND CO</i>	
13.33	STA 804+51.00 - 804+56.00	5' X 24'
28.88	STA 805+01.00 - 805+11.83	10.83' X 24'
13.33	STA 195+90.00 - 195+95.00	5' X 24'
13.33	STA 196+73.00 - 196+78.00	5' X 24'
13.33	STA 477+30.00 - 477+35.00	5' X 24'
13.33	STA 478+18.00 - 478+23.00	5' X 24'
13.33	STA 711+70.00 - 711+75.00	5' X 24'
	<i>RAMPS (EAST BOUND) ROCK ISLAND CO</i>	
	I-88 & I-80 SW RAMP 2 (EXIT)	
240.67	STA 1370+00.00 - 1372+00.00	10.83' X 200'
19.25	STA 1392+31.17 - 1392+42.00	10.83' X 16'
	I-88 & I-80 SW RAMP 1 (ENTRANCE)	
19.25	STA 1047+08.00 - 1047+18.83	10.83' X 16'
	I-88 & I-80 SOUTH WEAVE LANE 1	
361.00	STA 1049+69.00 - 1052+69.00	10.83' X 300'
240.67	STA 1061+30.00 - 1063+30.00	10.83' X 200'
	I-88 & I-80 SE RAMP 1 (EXIT)	
19.25	STA 1076+78.17 - 1076+89.00	10.83' X 16'
	SE RAMP 2 (ENTRANCE)	
19.25	STA 1109+56.00 - 1109+66.83	10.83' X 16'
	I-88 & I-80 SOUTH WEAVE LANE 2	
361.00	STA 1128+83.00 - 1131+83.00	10.83' X 300'
240.67	STA 1135+87.00 - 1137+87.00	10.83' X 200'
	OLD IL 2 SW RAMP (EXIT)	
14.81	STA 1165+91.67 - 1166+00.00	8.33' X 16'
	OLD IL 2 SE RAMP (ENTRANCE)	
14.81	STA 5401+88.00 - 5401+96.33	8.33' X 16'
361.00	STA 5414+16.00 - 5417+16.00	10.83' X 300'
	IL 92 SE RAMP (EXIT)	
240.67	STA 4975+48.00 - 4977+48.00	10.83' X 200'
19.25	STA 4998+57.67 - 4998+66.00	8.33' X 16'
	IL 92 NE RAMP (ENTRANCE)	
14.81	STA 5001+40.00 - 5001+48.33	8.33' X 16'
361.00	STA 5012+29.00 - 5015+29.00	10.83' X 300'
	MOLINE RD SE RAMP (EXIT)	
240.67	STA 5177+00.00 - 5179+00.00	10.83' X 200'
19.25	STA 5198+56.67 - 5198+65.00	8.33' X 16'
	MOLINE RD NE RAMP (ENTRANCE)	
14.81	STA 5201+26.00 - 5201+34.33	8.33' X 16'
361.00	STA 5211+58.00 - 5214+58.00	10.83' X 300'
	<i>RAMPS (WEST BOUND) ROCK ISLAND CO</i>	
	I-88 & I-80 NW RAMP 2 (ENTRANCE)	
19.25	STA 1329+21.00 - 1329+31.83	10.83' X 16'
361.00	STA 1349+00.00 - 1352+00.00	10.83' X 300'
	I-88 & I-80 NW RAMP 1 (EXIT)	
19.25	STA 1016+07.17 - 1016+18.00	10.83' X 16'
	I-88 & I-80 NORTH WEAVE LANE 1	
361.00	STA 1109+51.00 - 1112+51.00	10.83' X 300'
240.67	STA 1001+75.00 - 1003+75.00	10.83' X 200'
	I-88 & I-80 NE RAMP 1 (ENTRANCE)	
19.25	STA 1098+41.00 - 1098+51.83	10.83' X 16'
	I-88 & I-80 RAMP A-B	
361.00	STA 1300+60.00 - 1303+60.00	10.83' X 300'
	I-88 & I-80 NE RAMP 2	
192.53	STA 1209+26.00 - 1210+86.00	10.83' X 160'
19.25	STA 1235+22.17 - 1235+33.00	10.83' X 16'
	SOUTH WEAVE LANE 3	
361.00	STA 1280+00.00 - 1283+00.00	10.83' X 300'
	NORTH WEAVE LANE 3	
361.00	STA 1200+00.00 - 1203+00.00	10.83' X 300'
	RAMP C-D	
361.00	STA 1260+00.00 - 1263+00.00	10.83' X 300'