

HOT MIX ASPHALT SCHEDULE (EASTBOUND)

STATIONING	REMARKS	PAVEMENT			X4060115	40603243	40603545	44000155	44000162	X4401198
		LENGTH	WIDTH	AREA	P BIT MATLS PR CT 2 APPL.	2 1/4", POLY HMA BC, IL-19.0 FG, N90	1 1/2", POLY HMA SC, "D" N90	HMA SURF REM 1 1/2"	HMA SURF REM 3 1/4"	HMA SURF REM VAR
		FEET	FEET	SQ. YD.	POUND	TON	TON	SQ. YD	SQ. YD	SQ. YD
MAINLINE ROCK ISLAND CO.										
805+01.00 - 811+76.00	Normal	675.00	24.00	1800.00	2430.00	226.80	151.20		1800.00	
811+76.00 - 818+49.00	Normal (I80 SW R2)	673.00	24.00	1794.67	2422.80	226.13	150.75		1794.67	
818+49.00 - 826+38.00	Normal	789.00	24.00	2104.00	2840.40	265.10	176.74		2104.00	
826+38.00 - 828+76.00	Normal (I80 SW R1)	238.00	24.00	634.67	856.80	79.97	53.31		634.67	
828+76.00 - 832+25.00	Normal (Start S Weave 1)	349.00	24.00	930.67	1256.40	117.26	78.18		930.67	
832+25.00 = +.00	STA EQUATION	-	-	-	-	-	-	-	-	-
+ .00 - 3+14.00	Normal (End S Weave 1)	314.00	24.00	837.33	1130.40	105.50	70.34		837.33	
3+14.00 - 4+43.00	Normal (I80 SE R1)	129.00	24.00	344.00	464.40	43.34	28.90		344.00	
4+43.00 - 12+19.00	Normal	776.00	24.00	2069.33	2793.60	260.74	173.82		2069.33	
12+19.00 - 14+26.00	Normal (I80 SE R2)	207.00	24.00	552.00	745.20	69.55	46.37		552.00	
14+26.00 - 23+57.00	Normal (S Weave 2)	931.00	24.00	2482.67	3351.60	312.82	208.54		2482.67	
23+57.00 - 27+00.00	Normal (Old IL2 SW R)	343.00	24.00	914.67	1234.80	115.25	76.83		914.67	
27+00.00 - 38+30.00	Normal	1130.00	24.00	3013.33	4068.00	379.68	253.12		3013.33	
38+30.00 - 41+30.00	Normal (Under Old IL 2)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
41+30.00 - 51+38.00	Normal	1008.00	24.00	2688.00	3628.80	338.69	225.79		2688.00	
51+38.00 - 63+00.00	Normal (Old IL2 SE R)	1162.00	24.00	3098.67	4183.20	390.43	260.29		3098.67	
63+00.00 - 85+67.00	Normal	2267.00	24.00	6045.33	8161.20	761.71	507.81		6045.33	
85+67.00 - 88+67.00	Normal (Under 226th St.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
88+67.00 - 182+05.00	Normal	9338.00	24.00	24901.33	33616.80	3137.57	2091.71		24901.33	
182+05.00 - 185+05.00	Normal (Under 248th St.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
185+05.00 - 194+42.50	Normal	937.50	24.00	2500.00	3375.00	315.00	210.00		2500.00	
194+42.50 - 195+55.00	Normal (Taper 3.75"-1.5")	112.50	24.00	300.00	405.00	37.80	25.20			300.00
195+55.00 - 195+95.00	Normal (Mill & Res 1.5")	40.00	24.00	106.67	144.00		8.96	106.67		
195+95.00 - 196+73.00	Bridge Omission	78.00	-	-	-	-	-	-	-	-
196+73.00 - 197+13.00	Normal (Mill & Res 1.5")	40.00	24.00	106.67	144.00		8.96	106.67		
197+13.00 - 198+25.50	Normal (Taper 1.5"-3.75")	112.50	24.00	300.00	405.00		25.20			300.00
198+25.50 - 253+85.00	Normal	5559.50	24.00	14825.33	20014.20	1867.99	1245.33		14825.33	
253+85.00 - 256+85.00	Normal (Under 265th St.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
256+85.00 - 284+35.00	Normal	2750.00	24.00	7333.33	9900.00	924.00	616.00		7333.33	
284+35.00 - 290+98.00	Normal (IL92 SE R)	663.00	24.00	1768.00	2386.80	222.77	148.51		1768.00	
290+98.00 - 299+72.00	Normal	874.00	24.00	2330.67	3146.40	293.66	195.78		2330.67	
299+72.00 - 302+72.00	Normal (Under IL 92)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
302+72.00 - 314+60.00	Normal	1188.00	24.00	3168.00	4276.80	399.17	266.11		3168.00	
314+60.00 - 326+20.00	Normal (IL92 NE R)	1160.00	24.00	3093.33	4176.00	389.76	259.84		3093.33	
326+20.00 - 369+65.00	Normal	4345.00	24.00	11586.67	15642.00	1459.92	973.28		11586.67	
369+65.00 - 372+65.00	Normal (Under 286th St.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
372+65.00 - 434+58.00	Normal	6193.00	24.00	16514.67	22294.80	2080.85	1387.23		16514.67	
434+58.00 - 437+58.00	Normal (Under 66th Ave.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
437+58.00 - 471+25.00	Normal	3367.00	24.00	8978.67	12121.20	1131.31	754.21		8978.67	
471+25.00 - 476+37.50	Superelevated	512.50	24.00	1366.67	1845.00	172.20	114.80		1366.67	
476+37.50 - 477+50.00	Super (Taper 3.75"-1.5")	112.50	24.00	300.00	405.00	37.80	25.20			300.00
477+50.00 - 477+90.00	Super (Mill & Res 1.5")	40.00	24.00	106.67	144.00		8.96	106.67		
477+90.00 - 478+73.00	Bridge Omission	83.00	-	-	-	-	-	-	-	-
478+73.00 - 479+13.00	Super (Mill & Res 1.5")	40.00	24.00	106.67	144.00		8.96	106.67		
479+13.00 - 480+25.50	Super (Taper 1.5"-3.75")	112.50	24.00	300.00	405.00		25.20			300.00
480+25.50 - 525+03.00	Superelevated	4477.50	24.00	11940.00	16119.00	1504.44	1002.96		11940.00	
525+03.00 - 531+71.00	Normal (Moline Rd SE R)	668.00	24.00	1781.33	2404.80	224.45	149.63		1781.33	
531+71.00 - 539+02.50	Normal	731.50	24.00	1950.67	2633.40	245.78	163.86		1950.67	
539+02.50 - 540+90.00	Normal (Taper 3.75"-0")	187.50	24.00	500.00	675.00	63.00	42.00			500.00
540+90.00 - 543+90.00	Omission Under Moline Rd.	300.00	-	-	-	-	-	-	-	-
543+90.00 - 545+77.50	Normal (Taper 0"-3.75")	187.50	24.00	500.00	675.00	63.00	42.00			500.00
545+77.50 - 553+20.00	Normal	742.50	24.00	1980.00	2673.00	249.48	166.32		1980.00	
553+20.00 - 558+07.50	Normal (Start Moline NE R)	487.50	24.00	1300.00	1755.00	163.80	109.20		1300.00	
558+07.50 - 559+20.00	Normal (Taper 3.75"-1.5")	112.50	24.00	300.00	405.00	37.80	25.20			300.00
559+20.00 - 561+70.00	Normal (Under 94th, 1.5")	250.00	24.00	666.67	900.00		56.00	666.67		
561+70.00 - 562+82.50	Normal (Taper 1.5"-3.75")	112.50	24.00	300.00	405.00	37.80	25.20			300.00
562+82.50 - 564+81.00	Normal (End Moline NE R)	198.50	24.00	529.33	714.60	66.70	44.46		529.33	
564+81.00 - 571+64.00	Normal	683.00	24.00	1821.33	2458.80	229.49	152.99		1821.33	
571+64.00 - 620+81.00	Superelevated	4917.00	24.00	13112.00	17701.20	1652.11	1101.41		13112.00	
620+81.00 - 630+16.50	Normal	935.50	24.00	2494.67	3367.80	314.33	209.55		2494.67	
630+16.50 - 632+04.00	Normal (Taper 3.75"-0")	187.50	24.00	500.00	675.00	63.00	42.00			500.00
632+04.00 - 634+54.00	Omission Under 317th St.	250.00	-	-	-	-	-	-	-	-
634+54.00 - 636+41.50	Normal (Taper 0"-3.75")	187.50	24.00	500.00	675.00	63.00	42.00			500.00
636+41.50 - 673+35.00	Normal	3693.50	24.00	9849.33	13296.60	1241.02	827.34		9849.33	
686+37.00 - 702+01.00	Normal	1564.00	24.00	4170.67	5630.40	525.50	350.34		4170.67	
702+01.00 - 703+93.00	Superelevated	192.00	24.00	512.00	691.20	64.51	43.01		512.00	
703+93.00 - 706+93.00	Super (Under 122nd Ave.)	300.00	24.00	800.00	1080.00	100.80	67.20		800.00	
706+93.00 - 708+88.50	Superelevated	195.50	24.00	521.33	703.80	65.69	43.79		521.33	
708+88.50 - 710+01.00	Super (Taper 3.75"-1.5")	112.50	24.00	300.00	405.00	37.80	25.20			300.00
710+01.00 - 710+41.00	Super (Mill & Res 1.5")	40.00	24.00	106.67	144.00		8.96	106.67		
710+41.00 - 712+67.00	Bridge Omission	226.00	-	-	-	-	-	-	-	-
712+67.00 - 713+11.00	Super (Mill & Res 1.5")	44.00	24.00	117.33	158.40		9.86	117.33		
SUB TOTAL:					258465.60	23957.47	16082.30	1317.33	186038.67	4100.00

NOTE:
PLEASE VERIFY RAMPS SCHEDULES FOR HMA
& AGG SHOULLDER GAPS IN THIS SCHEDULE

FILE NAME =	USER NAME = diaza	DESIGNED -	REVISED -				
Default	Dr:\Projects\Rock_Island\64065.1-88_Cold Milling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line\Maris	REVISED FINAL\64065.dgn				
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -				
	PLOT DATE = Wed Mar 19 11:10:00 2014	DATE -	REVISED -				

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

HMA SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	(161-1) RS-1	ROCK ISLAND	104	27
CONTRACT NO. 64065				
ILLINOIS FED. AID PROJECT				