

HOT MIX ASPHALT SCHEDULE (EASTBOUND)

STATIONING	REMARKS	PAVEMENT			X4060115	40603243	40603545	44000155	44000162
		LENGTH	WIDTH	AREA	P BIT MATLS PR CT 2 APPL.	2 1/4", POLY HMA BC, IL-19.0 FG, N90	1 1/2", POLY HMA SC, "D" N90	HMA SURF REM 1 1/2"	HMA SURF REM 3 1/4"
		FEET	FEET	SQ. YD.	POUND	TON	TON	SQ. YD	SQ. YD
MAINLINE WHITESIDE CO.									
673+35.00 - 686+37.00	Normal	1302.00	24.00	3472.00	4687.20	437.47	291.65		3472.00
713+11.00 - 713+96.00	Super (Mill & Res 1.5")	85.00	24.00	226.67	306.00		19.04	226.67	
SUB TOTAL:					4993.20	437.47	310.69	226.67	3472.00

STATIONING	REMARKS	HMA SHOULDER					X4060115	40603310	40603310	44000153	AGGREGATE SHOULDER					48102100
		LENGTH	OUTSIDE (RT)		INSIDE (LT)		P BIT MATLS PR CT 1 APPL.	1", HMA SC, "C" N50	1 1/2", HMA SC, "C" N50	HMA SURF REM 1"	OUT (RT)	IN (LT)	LENGTH	WIDTH	DEPTH	AGG WEDGE SHLD T-B TON
			WIDTH	AREA	WIDTH	AREA										
FEET	FEET	SQ. YD.	FEET	SQ. YD.	POUND	TON	TON	SQ YD			FEET	FEET	FEET			
MAINLINE WHITESIDE CO.																
673+35.00 - 686+37.00	Normal	1302.00	10.00	1446.67	6.00	868.00	1562.40		194.43	2314.67	X	X	1302.00	4.00	0.13	148.28
713+11.00 - 713+96.00	Super (Mill & Res 1.5")	85.00	10.00	94.44	6.00	56.67	102.00	8.46		151.11	X	X	85.00	4.00	0.08	6.45
SUB TOTAL:							1664.40	8.46	194.43	2465.78						154.74

NOTE:
PLEASE VERIFY RAMPS SCHEDULES FOR HMA
& AGG SHOULLDER GAPS IN THIS SCHEDULE

FILE NAME =	USER NAME = diaza	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HMA SCHEDULE	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0:\Projects\Rock_Island\64065.1-88_Cold	milling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line\Mar	REVISED \FINAL\64065.dgn			88	(161-1) RS-1	ROCK ISLAND	104	29				CONTRACT NO. 64065		
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -						ILLINOIS FED. AID PROJECT							