

HOT MIX ASPHALT SCHEDULE (WESTBOUND)

STATIONING	REMARKS	PAVEMENT			X4060115	40603243	40603545	44000155	44000162
		LENGTH	WIDTH	AREA	P BIT MATLS	2 1/4", POLY HMA	1 1/2", POLY HMA	HMA SURF	HMA SURF
					PR CT 2 APPL.	BC, IL-19.0 FG, N90	SC, "D" N90	REM 1 1/2"	REM 3 1/4"
FEET	FEET	SQ. YD.	POUND	TON	TON	SQ. YD	SQ. YD		
MAINLINE WHITESIDE CO.									
673+35.00 - 686+37.00	Normal	1302.00	24.00	3472.00	4687.20	437.5	291.6	3472.0	
714+10.00 - 715+36.00	Super (Mill & Res 1.5")	126.00	24.00	336.00	453.60		28.2	336.0	
				SUB TOTAL:	5140.80	437.47	319.87	3472.00	

STATIONING	REMARKS	HMA SHOULDER					X4060115	40603310	40603310	44000153	AGGREGATE SHOULDER					48102100
		LENGTH	OUTSIDE (RT)		INSIDE (LT)		P BIT MATLS PR CT 1 APPL.	1", HMA SC "C" N50	1 1/2", HMA SC "C" N50	HMA SURF REM 1"	OUT (RT)	IN (LT)	LENGTH	WIDTH	DEPTH	AGG WEDGE SHLD T-B TON
			WIDTH	AREA	WIDTH	AREA										
FEET	FEET	SQ. YD.	FEET	SQ. YD.	POUND	TON	TON	SQ YD	FEET	FEET	FEET	TON				
MAINLINE WHITESIDE CO.																
673+35.00 - 686+37.00	Normal	1302.00	10.00	1446.67	6.00	868.00	1562.40	194.4	2314.7	X	X	1302.00	4.00	0.13	148.28	
714+10.00 - 715+36.00	Super (Mill & Res 1.5")	126.00	10.00	140.00	6.00	84.00	151.20	12.5	224.0	X	X	126.00	4.00	0.08	9.57	
						SUB TOTAL:	1713.60	12.54	194.43	2538.67					157.9	

NOTE:
PLEASE VERIFY RAMPS SCHEDULES FOR HMA
& AGG SHOULLDER GAPS IN THIS SCHEDULE

FILE NAME =	USER NAME = diaza	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	HMA SCHEDULE	SCALE:	SHEET OF SHEETS	STA. TO STA.
0:\Projects\Rock_Island\64065.1-88_Cold	milling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line\Mar	REVISED \FINAL\64065.dgn					
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -					
	PLOT DATE = Wed Mar 19 11:12:05 2014	DATE -	REVISED -					

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
88	(161-1) RS-1	ROCK ISLAND	104	32
CONTRACT NO. 64065				
ILLINOIS FED. AID PROJECT				