

PAVEMENT MARKING SCHEDULE (MAIN LINE)

(ROCK ISLAND CO.)

STATIONING	REMARKS	64200116		78009004				78009006		X7830070	X7830074	78100100	78300200	70300100			70301000	
		SHOULDER RUMBLE STRIPS, 16 INCH		MODIFIED URETHANE PAVEMENT MARKING - LINE 4"				MODIFIED URETHANE PAVEMENT MARKING - LINE 6"		GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING ** (3 APPLICATIONS)			WORK ZONE PAVEMENT MARKING REMOVAL	
		FOOT		FOOT		FOOT		FOOT	FOOT	EACH	EACH	RRPM REMARKS	FOOT			SQ FT		
		WHITE SOL	YELLOW SOL	WHITE SKIP								WHITE CL SKIP	WHITE RT EOP DIA	YELLOW LT EOP DIA				
MAINLINE EASTBOUND																		
805+01.00 - 811+76.00		1,350	RT & LT	675	RT	675	LT	169	CL	1,350	169	8	8	OW CRYSTAL 80' o.c..	507	81	81	74
811+76.00 - 818+49.00	I-80 SW R 2	673	LT			673	LT	168	CL	673	168	8	8	OW CRYSTAL 80' o.c..	507		81	65
818+49.00 - 826+38.00		1,578	RT & LT	789	RT	789	LT	197	CL	1,578	197	10	10	OW CRYSTAL 80' o.c..	594	96	96	87
826+38.00 - 832+25.00	I-80 SW R 1 - S WEAVE 1	587	LT			587	LT	147	CL	587	147	7	7	OW CRYSTAL 80' o.c..	441		72	57
832+25.00 0+00.00	STA. EQN.																	0
0+00.00 - 4+98.00	S WEAVE 1 - I-80 SE R 1	498	LT			498	LT	125	CL	498	125	6	6	OW CRYSTAL 80' o.c..	375		60	48
4+98.00 - 12+19.00		1,442	RT & LT	721	RT	721	LT	180	CL	1,442	180	9	9	OW CRYSTAL 80' o.c..	543	87	87	80
12+19.00 - 27+50.00	I-80 SE 2-S WEAVE 2-Old IL-2 S	1,531	LT			1,531	LT	383	CL	1,531	383	19	19	OW CRYSTAL 80' o.c..	1149		186	148
27+50.00 - 51+38.00		4,776	RT & LT	2,388	RT	2,388	LT	597	CL	4,776	597	30	30	OW CRYSTAL 80' o.c..	1791	288	288	263
51+38.00 - 63+00.00	OLD IL 2 SE RAMP	1,162	LT			1,162	LT	291	CL	1,162	291	15	15	OW CRYSTAL 80' o.c..	873		141	113
63+00.00 - 284+35.00		44,270	RT & LT	22,135	RT	22,135	LT	5,534	CL	44,270	5,534	277	277	OW CRYSTAL 80' o.c..	16602	2658	2658	2435
284+35.00 - 290+98.00	IL 92 SE RAMP	663	LT			663	LT	166	CL	663	166	8	8	OW CRYSTAL 80' o.c..	498		81	64
290+98.00 - 314+60.00		4,724	RT & LT	2,362	RT	2,362	LT	591	CL	4,724	591	30	30	OW CRYSTAL 80' o.c..	1773	285	285	260
314+60.00 - 326+20.00	IL 92 NE RAMP	1,160	LT			1,160	LT	290	CL	1,160	290	15	15	OW CRYSTAL 80' o.c..	870		141	112
326+20.00 - 525+03.00		39,766	RT & LT	19,883	RT	19,883	LT	4,971	CL	39,766	4,971	249	249	OW CRYSTAL 80' o.c..	14913	2388	2388	2188
525+03.00 - 531+71.00	MOLINE RD. SE RAMP	668	LT			668	LT	167	CL	668	167	8	8	OW CRYSTAL 80' o.c..	501		81	65
531+71.00 - 553+20.00		4,298	RT & LT	2,149	RT	2,149	LT	537	CL	4,298	537	27	27	OW CRYSTAL 80' o.c..	1614	258	258	237
553+20.00 - 564+81.00	MOLINE RD. NE RAMP	1,161	LT			1,161	LT	290	CL	1,161	290	15	15	OW CRYSTAL 80' o.c..	873		141	113
564+81.00 - 673+35.00		21,708	RT & LT	10,854	RT	10,854	LT	2,714	CL	21,708	2,714	136	136	OW CRYSTAL 80' o.c..	8142	1305	1305	1195
673+35.00 - 686+37.00		5,348	RT & LT	2,674	RT	2,674	LT	669	CL	5,348	669	33	33	OW CRYSTAL 80' o.c..	2007	321	321	294
MAINLINE WESTBOUND																		
805+01.00 - 806+97.00		392	RT & LT	196	RT	196	LT	49	CL	392	49	2	2	OW CRYSTAL 80' o.c..	147	24	24	22
806+97.00 - 819+55.00	I-80 NW R 2	1,258	LT			1,258	LT	315	CL	1,258	315	16	16	OW CRYSTAL 80' o.c..	945		153	122
819+55.00 - 826+64.00		1,418	RT & LT	709	RT	709	LT	177	CL	1,418	177	9	9	OW CRYSTAL 80' o.c..	534	87	87	79
826+64.00 - 832+25.00	I-80 NW 1 - N WEAVE 1	561	LT			561	LT	140	CL	561	140	7	7	OW CRYSTAL 80' o.c..	423		69	55
832+25.00 0+00.00	STA. EQN.																	0
0+00.00 - 17+67.00	N WEAVE 1 - I-80 NE 1 - A-B	1,767	LT			1,767	LT	442	CL	1,767	442	22	22	OW CRYSTAL 80' o.c..	1326		213	171
17+67.00 - 34+44.00		3,354	RT & LT	1,677	RT	1,677	LT	419	CL	3,354	419	21	21	OW CRYSTAL 80' o.c..	1260	204	204	185
34+44.00 - 41+16.00	RAMP C-D	672	LT			672	LT	168	CL	672	168	8	8	OW CRYSTAL 80' o.c..	504		81	65
41+16.00 - 50+48.00		1,864	RT & LT	932	RT	932	LT	233	CL	1,864	233	12	12	OW CRYSTAL 80' o.c..	699	114	114	103
50+48.00 - 57+11.00	OLD IL 2 NE RAMP	663	LT			663	LT	166	CL	663	166	8	8	OW CRYSTAL 80' o.c..	498		81	64
57+11.00 - 275+16.00		43,610	RT & LT	21,805	RT	21,805	LT	5,451	CL	43,610	5,451	273	273	OW CRYSTAL 80' o.c..	16356	2619	2619	2399
275+16.00 - 286+76.00	IL 92 SW	1,160	LT			1,160	LT	290	CL	1,160	290	15	15	OW CRYSTAL 80' o.c..	870		141	112
286+76.00 - 310+38.00		4,724	RT & LT	2,362	RT	2,362	LT	591	CL	4,724	591	30	30	OW CRYSTAL 80' o.c..	1773	285	285	260
310+38.00 - 317+00.00	IL 92 NW	662	LT			662	LT	166	CL	662	166	8	8	OW CRYSTAL 80' o.c..	498		81	64
317+00.00 - 519+25.00		40,450	RT & LT	20,225	RT	20,225	LT	5,056	CL	40,450	5,056	253	253	OW CRYSTAL 80' o.c..	15171	2427	2427	2225
519+25.00 - 530+83.00	MOLINE RD. SW RAMP	1,158	LT			1,158	LT	290	CL	1,158	290	14	14	OW CRYSTAL 80' o.c..	870		141	112
530+83.00 - 552+33.00		4,300	RT & LT	2,150	RT	2,150	LT	538	CL	4,300	538	27	27	OW CRYSTAL 80' o.c..	1614	258	258	237
552+33.00 - 558+96.00	MOLINE RD. NW RAMP	663	LT			663	LT	166	CL	663	166	8	8	OW CRYSTAL 80' o.c..	498		81	64
558+96.00 - 673+35.00		22,878	RT & LT	11,439	RT	11,439	LT	2,860	CL	22,878	2,860	143	143	OW CRYSTAL 80' o.c..	8580	1374	1374	1259
673+35.00 - 686+37.00		5,348	RT & LT	2,674	RT	2,674	LT	669	CL	5,348	669	33	33	OW CRYSTAL 80' o.c..	2007	321	321	294
SUB TOTAL:		274,265		128,799		145,466		36,367		274,265	36,367	1,819	1,819		109,146	15,480	17,505	15,792

**SHORT TERM PAVEMENT MARKING FOR CENTERLINE SHALL BE PLACED ACCORDING TO 780001.

FILE NAME =	USER NAME = diaza	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Q:\Projects\Rock_Island\64065_I-88_Cold Milling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line\Mar's	REVISED	REVISED			88	(161-1) RS-1	ROCK ISLAND	104	46
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 64065		ILLINOIS FED. AID PROJECT		
	PLOT DATE = Wed Mar 19 11:16:37 2014	DATE -	REVISED -	SCALE:	SHEET OF SHEETS	STA.	TO STA.			