

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% LOCAL	80% FEDERAL 20% STATE	100% MOLINE	
				ROADWAY	ROADWAY	ROADWAY	ROADWAY	ROADWAY	UTILITY	
				0004	0004	0004	0028	0004	0043	
				URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	
28000500	INLET AND PIPE PROTECTION	EACH	2		2					
28000510	INLET FILTERS	EACH	39		39					
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	688	688						
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	16,891	16,891						
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	16,580	16,580						
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	1,148				1,148			
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	1,611				1,320		291	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	140				115		25	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	730	730						
40603415	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, N50	TON	253				228		25	
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	277	277						
42000406	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/4" (JOINTED)	SQ YD	14,528	14,528						
42001300	PROTECTIVE COAT	SQ YD	16,306	16,306						



14

* SPECIALTY ITEM

DESIGNED	1/12/2014
DRAWN	1/12/2014
CHECKED	1/12/2014
REVIEWED	3/25/2014

FILE NAME	D2PACKE-HPS-shr-ganno10091.dgn
USER NAME	paxx00954
DESIGNED	- CBP
DRAWN	- CBP
CHECKED	- AAP
REVIEWED	-
PLOT SCALE	
PLOT DATE	03/25/2014
DATE	3/7/2014
REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	(B1-1)M	ROCK ISLAND	217	6
CONTRACT NO.			64J68	
ILLINOIS FED. AID PROJECT				

S00-02