

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% LOCAL	80% FEDERAL 20% STATE	100% MOLINE	
				ROADWAY	ROADWAY	ROADWAY	ROADWAY	ROADWAY	UTILITY	
				0004 URBAN	0004 URBAN	0004 URBAN	0028 URBAN	0004 URBAN	0043 URBAN	
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	8,161			4,701				3,460
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	270			270				
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	1,395			1,395				
* 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	2,030			1,805				225
* 81702190	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4/0	FOOT	285			285				
* 82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	1							1
* 82500370	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 200AMP	EACH	1			1				
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	130			52				78
* 83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	72			32				40
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	18							18
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	4			4				
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	22			4				18
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1							1
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1							1
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1				

15

* SPECIALTY ITEM



LAYOUT	CBP	3/5/2013
DRAWN	CBP	3/5/2014
REVIEWED	AAP	3/25/2014

FILE NAME * D2PACKE-HPS-ah1-gennoto0181.dgn

USER NAME * pax00954
 DESIGNED - CBP
 DRAWN - CBP
 CHECKED - AAP
 PLOT DATE * 03/25/2014

REVISED -
 REVISED -
 REVISED -
 REVISED -
 DATE - 3/7/2014

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	181-11M	ROCK ISLAND	217	15
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64J68	

Rev.

500-11