

20100110		
TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
STA. 507+73.5 / 10.7' LT	6	UNITS
STA. 507+80.7 / 11.2' LT	6	UNITS
STA. 3016+46.6 / 94.9' RT	10	UNITS
STA. 3016+56.2 / 86.5' RT	10	UNITS
STA. 3016+63.9 / 85.9' RT	10	UNITS
TOTAL	42	UNITS

20100210		
TREE REMOVAL (OVER 15 UNITS DIAMETER)		
STA. 507+49.0 / 16.4' LT	18	UNITS
TOTAL	18	UNITS

20200100		
EARTH EXCAVATION		
STA. 505+88.01 / 31.65' RT - 508+07.15 / 4.20' LT	40	CU YD
TOTAL	40	CU YD

20200200		
ROCK EXCAVATION		
SANITARY SEWER LOCATIONS		
STA. 505+80.4 / 0.0' - 519+20.4 / 0.0'	1,550	CU YD
TOTAL	1,550	CU YD

20800150		
TRENCH BACKFILL		
STA. 507+32.05 / 1.35' LT - 519+42.53 / 0.0'	4,000	CU YD
STA. 512+53.77 / 2.00' RT - 512+53.91 / 52.23' RT	69	CU YD
STA. 3005+58.85 / 30.63' RT - 3005+69.74 / 33.29' RT	6	CU YD
STA. 3006+70.73 / 35.67' RT - 3008+45.38 / 39.27' RT	139	CU YD
STA. 3014+90.91 / 82.76' RT - 3016+23.02 / 88.67' RT	104	CU YD
TOTAL	4,318	CU YD

21001000		
GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		
STA. 505+88.01 / 31.65' RT - 508+07.15 / 4.20' LT	291	SQ YD
TOTAL	291	SQ YD

25000210		
SEEDING, CLASS 2A		
STA. 505+80.40 / 0.0' - 508+06.53 / 5.73' LT	0.1	AC
STA. 3005+52.67 / 39.10 RT - 3006+78.52 / 40.39' RT	0.02	AC
STA. 3008+39.62 / 38.30' RT - 3014+97.64 / 90.57' RT	0.2	AC
STA. 3016+18.99 / 93.88' RT - 3020+13.32 / 60.82' RT	0.1	AC
TOTAL	0.5	AC

25100115		
MULCH, METHOD 2		
STA. 505+80.40 / 0.0' - 508+06.53 / 5.73' LT	0.1	AC
STA. 3005+52.67 / 39.10 RT - 3006+78.52 / 40.39' RT	0.02	AC
STA. 3008+39.62 / 38.30' RT - 3014+97.64 / 90.57' RT	0.2	AC
STA. 3016+18.99 / 93.88' RT - 3020+13.32 / 60.82' RT	0.1	AC
TOTAL	0.5	AC

35100500		
AGGREGATE BASE COURSE, TYPE A 6"		
STA. 505+88.01 / 31.65' RT - 508+07.15 / 4.20' LT	291	SQ YD
TOTAL	291	SQ YD

40603080		
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50		
STA. 505+88.01 / 31.65' RT - 508+07.15 / 4.20' LT	25	TON
TOTAL	25	TON

40603415		
HOT-MIX ASPHALT SURFACE COURSE, IL-9.5FG, N50		
STA. 505+88.01 / 31.65' RT - 508+07.15 / 4.20' LT	25	TON
TOTAL	25	TON

56100075		
DUCTILE IRON WATER MAIN TEE, 16" X 6"		
STA. 3009+38.9 / 56.5' RT	1	EA
STA. 3013+47.8 / 79.7' RT	1	EA
STA. 3016+61.5 / 71.7' RT	1	EA
TOTAL	3	EA

56100077		
DUCTILE IRON WATER MAIN TEE, 16" X 8"		
STA. 3017+27.3 / 54.4' RT	1	EA
TOTAL	1	EA

56103100		
DUCTILE IRON WATER MAIN, 8"		
STA. 3017+27.3 / 54.4' RT TO 3017+27.2 / 48.2' RT	7	LF
STA. 3017+27.1 / 40.6' RT TO 3017+20.4 / 40.8' RT	7	LF
STA. 3017+20.4 / 40.8' RT TO 3017+20.2 / 36.4' RT	5	LF
STA. 3017+27.2 / 48.2' RT TO 3017+27.1 / 40.6' RT	8	LF
TOTAL	27	LF

56103400		
DUCTILE IRON WATER MAIN 16"		
STA. 3005+63.4 / RT - 3006+76.2 / RT	113	LF
STA. 3006+76.2 / RT - 3008+41.7 / RT	166	LF
STA. 3008+41.7 / RT - 3008+63.9 / RT	32	LF
STA. 3008+63.9 / RT - 3009+09.2 / RT	46	LF
STA. 3009+07.5 / RT - 3009+31.2 / RT	24	LF
STA. 3009+30.0 / RT - 3009+51.2 / RT	22	LF
STA. 3009+51.2 / RT - 3012+53.7 / RT	303	LF
STA. 3012+53.7 / RT - 3012+80.5 / RT	30	LF
STA. 3012+80.5 / RT - 3013+31.2 / RT	52	LF
STA. 3013+31.2 / RT - 3013+92.9 / RT	62	LF
STA. 3013+92.9 / RT - 3016+42.9 / RT	252	LF
STA. 3016+42.9 / RT - 3016+78.0 / RT	53	LF
STA. 3016+78.0 / RT - 3020+12.3 / RT	335	LF
TOTAL	1,490	LF

56105000		
WATER VALVES 8"		
STA. 3017+27.2 / 48.2' RT	1	EA
TOTAL	1	EA

56105300		
WATER VALVES 16"		
STA. 3017+19.9 / 54' RT	1	EA
TOTAL	1	EA