



**SUMMARY OF ITS QUANTITIES**

Pay Code	Item	Unit	Estimated Total	As Built Quan.
*2000293*	REMOVE AND REPLACE ITS EQUIPMENT	EACH	2	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	1.0	
73302170	OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A (36"x5'-6")	FOOT	28	
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	13.0	
80500200	SERVICE INSTALLATION, TYPE B	EACH	1	
80500300	SERVICE INSTALLATION, TYPE C	EACH	2	
81020750	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2" DIA.	FOOT	1940	
81400100	HANDHOLE	EACH	8	
X8140105*	HANDHOLE SPECIAL	EACH	5	
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	270	
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	1395	
81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	1710	
87301105	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 12 1C	FOOT	1015	
X0323920*	POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	2	
X0325482*	REMOVE EXISTING ITS EQUIPMENT	EACH	1	

\* NON-STANDARD PAY ITEM - SEE SPECIAL PROVISIONS

**LISTING OF ITS HANDHOLE WORK**

HANDHOLE LABEL	HANDHOLE TYPE	#2 Power Coil	#4 Ground Coil	#4 Power Coil	#6 Ground Coil
HH4-1	SPECIAL				
HH4-2	HANDHOLE			140	70
HH5-1	HANDHOLE				
HH5-2	HANDHOLE	140	70		
HH5-3	SPECIAL				
HH5-4	SPECIAL				
HH5-5	SPECIAL				
HH5-6	HANDHOLE				
HH5-7	HANDHOLE				
HH5-8	HANDHOLE				
HH5-9	HANDHOLE				
HH6-1	SPECIAL				
HH6-2	HANDHOLE	140	70		

**LISTING OF ITS CABINET WORK**

Cabinet Label	Sheet Number	Cabinet Type	Pole Mount	Pad Mount
CABINET 1	ITS-04	DMS	X	
CABINET 2	ITS-06	DMS	X	

**LISTING OF ITS CONDUIT WORK**

Conduit Run	Location		Conduit Length	Install 2" Conduit	Install #2 Power	Install #4 Ground	Install #4 Power	Install #6 Ground	Install #12 Tracer
	From	To							
4A	DMS POLE 1	HH4-1	10	1					1
4B	DMS POLE 1	HH4-2	10	1			2	1	
4C	HH4-1/HH4-2	HH5-1	155	2			2	1	1
5A	HH5-1	POWER SERVICE A	35	1			2	1	
5B	HH5-1	HH5-2	130	1					1
5C	HH5-2	EXISTING EMS	5	1	2	1			
5D	HH5-2	HH5-3	160	2	2	1			1
5E	HH5-3	HH5-4	160	1					1
5F	HH5-4	HH5-5	170	1					1
5G	HH5-5/HH5-6	HH6-1/HH6-2	220	2	2	1			1
5H	HH5-3	HH5-7	35	1	2	1			
5I	HH5-7	AUTOMATED GATE	5	1					
5J	HH5-7	HH5-8	65	1	2	1			
5K	HH5-8	AUTOMATED GATE	5	1					
5L	HH5-8	TEMP. POWER	85	1	2	1			
5M	HH5-6	HH5-9	125	1	2	1			
5N	HH5-9	POWER SERVICE B	10	1	2	1			
6A	HH6-1	DMS POLE 2	10	1					1
6B	HH6-2	DMS POLE 2	10	1	2	1			

LAYOUT	
DRAWN	
REVIEWED	

FILE NAME =	USER NAME = dmcolntock	DESIGNED - DJM	REVISED -
ci:\pwise_work\do_not_delete\dms01359\02PACKAGE-IT-shht-ITS500.shht		DRAWN - DJM	REVISED -
	PLOT SCALE = NA	CHECKED - SPG	REVISED -
	PLOT DATE = 4/14/2014	DATE - 3/6/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ITS QUANTITIES**

SCALE: NA SHEET NO. 1 110F SHEETSSTA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	(81-11M)	ROCK ISLAND	217	127
			CONTRACT NO. 64J68	
ILLINOIS FED. AID PROJECT				

ITS-01