

PATCHING SCHEDULE						
LOCATION	WIDTH FOOT	LENGTH FOOT	CLASS D	CLASS B		
			14" TYPE II SQ YD	SAW CUTS FOOT	DOWEL BARS 1 1/2" DIA EACH	8" TYPE II SQ YD
EACH CLASS D PATCH	13	6	8.7			
EACH CLASS B PATCH	12	6		48	20	8.0
4+43 TO 296+30	58 PATCHES		504.6			
296+30 TO 302+17	28 PATCHES			1344	560	224
304+43 TO 310+00	10 PATCHES			480	200	80
310+00 TO 383+08	46 PATCHES		400.2			
TOTALS			905	1824	760	304

SIDEWALK RAMP SCHEDULE											
LOCATION	EARTH EXC	FURN EXC	EROS CONT BLKT	SW REM	PCC SDWK 4"	DETECT WARN	INCID HMA SURF	BIT MATLS (PR CT)	PIPE DRAIN 8"	P CULV CL D, TY 1	END SECT 15"
	CU YD	CU YD	SQ YD	SQ FT	SQ FT	SQ FT	TON	GAL	FOOT	FOOT	EACH
MAIN ST INTERSECTION											
STA 18+70 LT	0.3			40	40	8	0.7	1.2			
STA 18+70 RT	0.2			40	40	8	0.4	0.6			
WHITE ST INTERSECTION											
STA 22+15 LT	0.3	1	4	40	40	8	0.7	1.2	5		
STA 22+15 RT	0.3	1	9	80	80	8	0.7	1.2		6	2
TOTALS	1	2	13	200	200	32	3	4	5	6	2