

CONSTR. CODE

80% FED.
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				0005	RURAL
20400800	FURNISHED EXCAVATION	CU YD	48	48	
25200110	SODDING, SALT TOLERANT	SO YD	10	10	
25200200	SUPPLEMENTAL WATERING	UNIT	0.1	0.1	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	23	23	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	39	39	
40600627	LEVELING BINDER (MACHINE METHOD), 1L-9, 5FG, N50	TON	3286	3286	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600990	TEMPORARY RAMP	SO YD	1424	1424	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6571	6571	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	647	647	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	50	50	
42400800	DETECTABLE WARNINGS	SO FT	16	16	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	78228	78228	
44000600	SIDEWALK REMOVAL	SO FT	25	25	

14

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FH.FL#		DRAWN -	REVISED -					1249	23RS-7	BUREAU	16	3	
#MODELNAME#		CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 66A02		
		DATE -	REVISED -								ILLINOIS FED. AID PROJECT		