

URBAN
CONSTR. CODE
90% FED,
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0005 RURAL
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	13604	13604
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	31829	31829
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	5199	5199
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	40	40
42001200	PAVEMENT FABRIC	SO YD	4154	4154
44000100	PAVEMENT REMOVAL	SO YD	7	7
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	53369	53369
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	11924	11924
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SO YD	115981	115981
44004250	PAVED SHOULDER REMOVAL	SO YD	21254	21254
44004000	PAVED DITCH REMOVAL	FOOT	711.5	711.5
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SO YD	1425	1425
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SO YD	272	272
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SO YD	124	124

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	80	150-4,5RS-4	LASALLE	54	4
	PLOT SCALE * #SCALE#	CHECKED -	REVISED -												
	PLOT DATE * #DATE#	DATE -	REVISED -												
CONTRACT NO. 66A35													ILLINOIS FED. AID PROJECT		