

CLASS B PATCHES 15" (WESTBOUND)									
STATION	MP	LANE	TYPE II	TYPE III	TYPE IV	PVMT FABRIC	TIE BARS	DOWEL BARS	SAW CUTS
			SOYD	SOYD	SOYD	SOYD	EACH	EACH	FOOT
LASALLE CO									
604+58	92.56	PASS LN	11			22		20	52
605+64	92.58	PASS LN	8			16		20	48
605+64	92.58	DRIVE LN	8			16		20	48
606+69	92.60	PASS LN	8			16		20	48
606+69	92.60	DRIVE LN	8			16		20	48
607+75	92.62	DRIVE LN	11			22		20	52
611+97	92.70	DRIVE LN	8			16		20	48
613+03	92.72	DRIVE LN	8			16		20	48
614+61	92.75	DRIVE LN	8			16		20	48
619+89	92.85	DRIVE LN	8			16		20	48
625+17	92.95	DRIVE LN	8			16		20	48
628+87	93.02	DRIVE LN	11			22		20	52
633+09	93.10	DRIVE LN	14			28		20	56
638+90	93.21	PASS LN	11			22		20	52
638+90	93.21	DRIVE LN	11			22		20	52
639+96	93.23	DRIVE LN	11			22		20	52
640+48	93.24	DRIVE LN	11			22		20	52
641+01	93.25	DRIVE LN	14			28		20	56
641+01	93.25	PASS LN	14			28		20	56
641+54	93.26	DRIVE LN	14			28		20	56
641+54	93.26	PASS LN	14			28		20	56
642+07	93.27	DRIVE LN	11			22		20	52
643+12	93.29	DRIVE LN			28	56	10	20	78
643+65	93.30	DRIVE LN			40	80	15	20	96
644+18	93.31	PASS LN	11			22		20	52
644+71	93.32	DRIVE LN		16		32		20	60
645+24	93.33	DRIVE LN	11			22		20	52
645+76	93.34	DRIVE LN		15		30		20	58
646+29	93.35	DRIVE LN		16		32		20	60
646+82	93.36	DRIVE LN		15		30		20	58
647+88	93.38	DRIVE LN	14			28		20	56
648+93	93.40	PASS LN	12			24		20	54
649+46	93.41	DRIVE LN	11			22		20	52
649+99	93.42	DRIVE LN	8			16		20	48
650+52	93.43	DRIVE LN	16	16		64		20	60
652+10	93.46	DRIVE LN	14			28		20	56
SUB TOTALS			327	78	68	946	25	720	1968

CLASS B PATCHES 15" (WESTBOUND)									
STATION	MP	LANE	TYPE II	TYPE III	TYPE IV	PVMT FABRIC	TIE BARS	DOWEL BARS	SAW CUTS
			SOYD	SOYD	SOYD	SOYD	EACH	EACH	FOOT
LASALLE CO									
653+68	93.49	DRIVE LN	14			28		20	56
654+21	93.50	DRIVE LN	14			28		20	56
655+27	93.52	DRIVE LN	14			28		20	56
655+80	93.53	DRIVE LN	14			28		20	56
656+85	93.55	DRIVE LN	14			28		20	56
658+44	93.58	DRIVE LN	16	16		64		20	60
662+13	93.65	DRIVE LN	11			22		20	52
663+19	93.67	PASS LN	14			28		20	56
663+72	93.68	PASS LN	11			22		20	52
664+24	93.69	DRIVE LN		16		32		20	60
674+28	93.88	PASS LN	14			28		20	56
674+81	93.89	PASS LN	11			22		20	52
675+33	93.90	PASS LN	16	16		64		20	60
675+86	93.91	DRIVE LN		16		32		20	60
682+20	94.03	PASS LN	14			28		20	56
710+18	94.56	PASS LN	11			22		20	52
711+76	94.59	PASS LN	11			22		20	52
712+82	94.61	PASS LN	11			22		20	52
720+21	94.75	PASS LN		15		30		20	58
726+55	94.87	PASS LN	14			28		20	56
730+77	94.95	PASS LN	14			28		20	56
735+00	95.03	PASS LN	14			28		20	56
737+11	95.07	DRIVE LN	16	16		64		20	60
738+17	95.09	DRIVE LN	11			22		20	52
738+69	95.10	DRIVE LN	14			28		20	56
739+75	95.12	DRIVE LN	14			28		20	56
742+39	95.17	DRIVE LN		16		32		20	60
745+03	95.22	DRIVE LN		15		30		20	58
748+20	95.28	DRIVE LN	14			28		20	56
749+25	95.30	DRIVE LN	11			22		20	52
750+31	95.32	DRIVE LN	11			22		20	52
751+89	95.35	DRIVE LN	10			20		20	50
753+48	95.38	PASS LN	8			16		20	48
754+53	95.40	DRIVE LN	8			16		20	48
767+73	95.65	DRIVE LN	14			28		20	56
769+32	95.68	DRIVE LN	11			22		20	52
769+84	95.69	DRIVE LN	11			22		20	52
769+84	95.69	PASS LN	11			22		20	52
787+80	96.03	DRIVE LN	11			22		20	52
787+80	96.03	PASS LN	11			22		20	52
788+85	96.05	DRIVE LN	11			22		20	52
801+52	96.29	PASS LN	11			22		20	52
802+05	96.30	PASS LN	11			22		20	52
SUB TOTALS			471	126	0	1194	0	860	2346
TOTALS			798	204	68	2140	25	1580	4314

PAVEMENT MARKING					
STATION TO STATION	PREFORMED PLASTIC PVT MK TYPE B			POLYUREA PAVEMENT MARKING	
	6"	24"	LET &	4"	
	WHITE FOOT	WHITE FOOT	SYM** SO FT	WHITE FOOT	YELLOW FOOT
IL 71 ENTRANCE RAMP A				160	112
IL 71 EXIT RAMP B		25	86.7	200	140
IL 71 ENTRANCE RAMP C				160	112
IL 71 EXIT RAMP D		25	86.7	200	140
FOX RIVER BRIDGE	188			1500	1500
TOTALS				2,220	2,004

\* STA 614+43.13 BK = 614+40.60 AH  
 \*\*WRONG WAY ARROW-SEE DETAIL (AND OTHER TURN ARROWS)

PAVED DITCH				
LOCATION	PAVED DITCH REMOVAL	PAVED DITCH, TYPE B-22	INLETS TO BE ADJUSTED	CLEANING EXISTING INLETS
	FOOT	FOOT	EACH	EACH
LASALLE COUNTY				
STA 603+05 to STA 609+17.5	612.5	612.5		
STA 610+16 to STA 611+15	99	99		
STA 602+95			2	1
STA 610+19			1	1
TOTALS	711.5	711.5	3	2