

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	REMOVE AND REERECT SPBGR*	SPBGR, TYPE A	LONGSPAN GR-12'-6" SPAN	LONGSPAN GR-18'-9" SPAN	TBT TY 1 SPEC (TANG)	TBT TY 2	TBT TY 5	TBT TY 6	TBT TY 6B	G-RAIL MARK TYA	TERMINAL MARKER - DA	HTCMB FOOT	HTCMB TERMINALS EACH	CABLE GUARD MARKERS EACH
	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	EACH	EACH
LASALLE COUNTY															
STA 603+00 EBDL	665		637.5					1	1		11				
STA 602+00 EB MED	225		212.5					1			5				
STA 602+00 WB MED	272		212.5			1			1		5	1			
STA 608+00 WBDL	1285		1187.5			1			1		18	1			
STA 604+00-613+75 WB MED													925	2	21
STA 617+85-678+75 WB MED													6040	2	135
STA 619+00 EBDL	440		375			1		1			6	1			
STA 619+00 WBDL	413		350			1		1			6	1			
STA 639+50 WBDL	348		228		169	1		1			5	1			
STA 679+30-734+00 WB MED													5470	2	137
STA 733+50-785+00 WB MED													5150	2	129
STA 788+67-809+05 WB MED													2038	2	51
STA 711+75 EBDL	318		262.5			1		1			5	1			
STA 711+75 WBDL	316		262.5			1		1			5	1			
STA 735+15 EBDL	355		250			1				1	5	1			
STA 735+15 MED	48														
STA 735+15 WBDL	304		225			1				1	5	1			
STA 752+00 EBDL	317		148	163		1		1			5	1			
STA 752+00 WBDL	355		197	163		1		1			5	1			
STA 764+60 EBDL	298		237.5			1		1			5	1			
STA 764+60 WBDL	329		275			1		1			5	1			
STA 772+30 EBDL	308		107.5		169	1		1			5	1			
STA 772+30 WBDL	290		114.5		169	1		1			5	1			
STA 785+00 WBDL	247	247													
STA 785+00 WBPL	347	347													
STA 785+00 EBPL	334	334													
PROJECT TOTALS	7814	928	5283	326	507	15	13	2	2	2	106	15	19623	10	473

UNDER THE GUARDRAIL REMOVAL PAY ITEM, ANY EXISTING GUARDRAIL THAT IS ATTACHED TO STRUCTURES WILL NOT BE PAID FOR SEPERATELY BUT WILL BE PAID FOR AS GUARDRAIL REMOVAL.

ALL BOLT HOLES IN THE PIERS FROM THE REMOVAL OF THE EXISTING TRAFFIC BARRIER TERMINALS SHALL BE EPOXY GROUTED PRIOR TO THE INSTALLATION OF THE NEW TRAFFIC BARRIER TERMINALS.

* THIS ITEM INCLUDES REMOVING AND REERECTING THE 3 TBT, TYPE 1 (SPECIAL) END SECTIONS AND THE 3 TBT, T2 END SECTIONS-MEASUREMENTS SHALL BE FROM END OF TBT, T1 TO END OF TBT, T 2

STABILIZATION & SEEDING SCHEDULE

LOCATION	HMA SHLD 6"	FURNISHED EXCAVATION	SEEDING CLASS 2A	EROSION CONT. BLKT	NITROGEN FERT. NUT.	PHOSPHORUS FERT. NUT.	POTASSIUM FERT. NUT.	PERIMETER EROSION BARRIER*	INLET AND PIPE PROTECTION*	TEMPORARY SEEDING	PIPE UNDERDRAIN OUTLET EXT FOR 4" PIPE**
	SY	CU YD	ACRE	SO YD	POUND	POUND	POUND	FOOT	EACH	ACRE	EACH
LASALLE COUNTY											
STA 603+00 EBDL	223	32	0.08	387	7.2	7.2	7.2	20		0.08	
STA 602+00 EB MED	82	11	0.03	145	2.7	2.7	2.7			0.03	
STA 602+00 WB MED	104	16	0.04	194	3.6	3.6	3.6			0.04	
STA 608+00 WBDL	428	62	0.17	823	15.3	15.3	15.3	20		0.17	
STA 619+00 EBDL	146	22	0.06	290	5.4	5.4	5.4			0.06	
STA 619+00 WBDL	138	21	0.05	242	4.5	4.5	4.5			0.05	
STA 639+50 WBDL	153	18	0.05	242	4.5	4.5	4.5		1	0.05	
STA 711+75 EBDL	109	17	0.05	242	4.5	4.5	4.5	40	1	0.05	
STA 711+75 WBDL	109	17	0.05	242	4.5	4.5	4.5	40		0.05	
STA 735+15 EBDL	114	18	0.05	242	4.5	4.5	4.5		2	0.05	
STA 735+15 WBDL	106	17	0.04	194	3.6	3.6	3.6			0.04	
STA 752+00 EBDL	124	17	0.05	242	4.5	4.5	4.5	40	1	0.05	
STA 752+00 WBDL	140	19	0.05	242	4.5	4.5	4.5	40		0.05	
STA 764+60 EBDL	100	16	0.04	194	3.6	3.6	3.6	40	1	0.04	
STA 764+60 WBDL	112	18	0.05	242	4.5	4.5	4.5	40		0.05	
STA 772+30 EBDL	113	16	0.04	194	3.6	3.6	3.6	40	1	0.04	
STA 772+30 WBDL	115	16	0.04	194	3.6	3.6	3.6	40		0.04	
STA 785+00 WBDL	87	16	0.04	194	3.6	3.6	3.6			0.04	
STA 785+00 WBPL	121	21	0.05	242	4.5	4.5	4.5			0.05	
STA 785+00 EBPL	116	19	0.05	242	4.5	4.5	4.5			0.05	
602+00 - 613+00 MEDIAN		SEE EARTHWORK	0.61	2953	54.9	54.9	54.9	25	1	0.61	2
662+00 - 669+00 MEDIAN		SEE EARTHWORK	0.39	1888	35.1	35.1	35.1	25	1	0.39	2
757+00 - 766+00 MEDIAN		SEE EARTHWORK	0.5	2420	45	45	45	25	1	0.5	2
795+00 - 807+00 MEDIAN		SEE EARTHWORK	0.66	3194	59.4	59.4	59.4	25	1	0.66	2
PROJECT TOTALS	2740	409	3.2	15682	292	292	292	460	11	3.2	8.0

ALL MATERIAL EXCAVATED FOR THE PLACEMENT OF THE HMA SHLD SHALL BE UTILIZED ON THE PROJECT ALONG THE FORESLOPES FROM WHICH IT WAS GENERATED. ALL WORK NECESSARY TO INCORPORATE AND SHAPE THIS MATERIAL SHALL BE INCIDENTAL TO THE HMA SHLD PAY ITEM. FURNISHED EX. TO BE PLACED ALONG FORESLOPE AT GUARDRAIL AND END SECTIONS LOCATIONS ACCORDING TO STD. 630301 THE HMA SHOULDER 6" PAY ITEM IS FOR GUARDRAIL STABILIZATION AS PER STANDARD 630201 *SEE PLAN SHEETS FOR EXACT PLACEMENT. PLACE INLET AND PIPE PROTECTION AT UPSTREAM LOCATION OF PIPE CULVERT **AS NEEDED-SEE DETAIL AND SPECIAL PROVISIONS

FILE NAME :	USER NAME : *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN -	REVISED -						80	150-4,5,RS-4	LASALLE	54	16
	PLOT SCALE : *SCALE*	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 66A35				
	PLOT DATE : *DATE*	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								