

SCHEDULE NORTHBOUND LANES PAVEMENT MARKING				
LOCATION	MODIFIED URETHANE PAVEMENT MARKING LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING TYPE B - 6"	GROOVING FOR RECESSED PAVEMENT MARKING 6"	MODIFIED URETHANE PAVEMENT MARKING LINE 8"
	FEET	FEET	FEET	FEET
STATION	YELLOW	WHITE	WHITE	WHITE
51+77	30	30	10	10
52+25	10	10	10	10
52+43	8	8	10	10
52+71	18	18	10	10
53+16	6	6	10	10
53+31	6	6	10	10
53+70	25	25	10	10
55+51		32	10	10
56+35	8	8	10	10
57+25	6	6	10	10
57+71	6	6	10	10
58+61	12	12	10	10
60+41	8	16	10	10
60+84	10	10	10	10
61+77	10	10	10	10
62+68		12	10	10
63+47		30	10	10
64+57		10	10	10
64+94		10	10	10
74+12	18	36	10	10
75+10	36	18	10	10
75+69		10	10	10
75+70	10			10
75+85	10	20	10	10
76+41	18	10	10	10
76+90		6		10
79+01		15	10	10
79+55	6		10	10
81+68		6	10	10
83+91	15	30	10	10
85+39	10	20	10	10
86+78	6	6	10	10
88+18	6	12	10	10
89+03	6		10	10
89+37	18	36	10	10
89+51		6		10
89+79	8	16	10	10
90+95	8	24	10	10
SUB TOTAL	338	536		
TOTAL	874		350	186

SCHEDULE SOUTHBOUND LANES PAVEMENT MARKING				
LOCATION	MODIFIED URETHANE PAVEMENT MARKING LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING TYPE B - 6"	GROOVING FOR RECESSED PAVEMENT MARKING TYPE B - 6"	MODIFIED URETHANE PAVEMENT MARKING LINE 8"
	FEET	FEET	FEET	FEET
STATION	YELLOW	WHITE	WHITE	WHITE
94+05	8	8	10	10
91+10	10	28	10	10
89+37	18	36	10	10
88+18	6	12	10	10
86+78	6	12	10	10
83+38	34	34	10	10
82+88	6	6	10	10
82+23	12	6	10	10
80+63	12	6	10	10
80+04	6		10	10
79+55	6	6	10	10
78+72	12	6	10	10
78+85	6	6	10	10
77+31	12	6	10	10
74+58	18	36	10	10
64+94	20	10	10	10
64+04	20	10	10	10
63+15	15		10	10
62+74	8		10	10
61+77	10	10	10	10
60+41	6	6	10	10
59+07	6	6	10	10
58+29	6	6	10	10
57+40	6	6	10	10
57+25	8	8	10	10
57+10	6	6	10	10
56+79	8	8	10	10
56+51	6	15	10	10
56+35	17	17	10	10
56+19	17	8	10	10
55+43	6	6	10	10
54+81	6	6	10	10
53+70	32	32	10	10
53+16	6	6	10	10
52+71	34	17	10	10
52+25	8	8	10	10
51+77	12	6	10	10
SUB TOTAL	435	405		
TOTAL	840		370	210

NORTHBOUND LANES PREFORMED PLASTIC PAVEMENT MARKING TYPE B - LETTERS, NUMBERS SYMBOLS & GROOVING		
SYMBOL TYPE	SIZE	QUANTITY
	SQ FT	EACH
LEFT OR RIGHT ARROW	15.6	14
TOTAL (SQ FT) GROOVING LT N & SYM		219
TOTAL (SQ FT) PREF PL PM TB LT & SYM		219

SOUTHBOUND LANES PREFORMED PLASTIC PAVEMENT MARKING TYPE B - LETTERS & SYMBOLS & GROOVING		
SYMBOL TYPE	SIZE	QUANTITY
	SQ FT	EACH
LEFT OR RIGHT ARROW	15.6	9
TOTAL (SQ FT) GROOVING LT, N, & SYM		141
TOTAL (SQ FT) PREF PL PM TB LT & SYM		141