

SCHEDULES
URBAN SOUTHBOUND MAINLINE PATCHING

LOCATION	PASS LANE	DRIVE LANE	PASSING LANE						DRIVING LANE					
			CLASS A 10"			PATCH REINF.	SAW CUTS	TIE BARS	CLASS A 10"			PATCH REINF.	SAW CUTS	TIE BARS
MILE POST	FOOT	FOOT	TYPE II SQ YD	TYPE III SQ YD	TYPE IV SQ YD				SQ YD	FOOT	EACH			
73.24		20									27	27	88	10
73.22		6							8			8	60	
73.20		6							8			8	60	
73.14		6							8			8	60	
73.01		35									47	47	118	17
57.43		45									60	60	138	22
54.51	6		8			8	60							
54.50		12								16		16	72	
54.49	30				40	40	108	15						
54.32	25	25			33	33	98	12			33	33	98	12
54.31		12								16		16	72	
54.29	6		8			8	60							
54.28		12								16		16	72	
54.21		6							8			8	60	
54.20		6							8			8	60	
SB URBAN SUBTOTALS			16		73	89	326	27	40	48	167	255	958	61

SOUTHBOUND TOTALS	CLASS A 10"			PATCH REINF.	SAW CUTS	TIE BARS
	TYPE II	TYPE III	TYPE IV			
	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH
	215	48	300	563	2526	110