

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				STATE 100% ROADWAY 0005 RURAL
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	248	248
44200545	CLASS A PATCHES, TYPE III, 9 INCH	SQ YD	80	80
44200547	CLASS A PATCHES, TYPE IV, 9 INCH	SQ YD	27	27
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	547	547
44200624	CLASS A PATCHES, TYPE III, 14 INCH	SQ YD	260	260
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	227	227
44213000	PATCHING REINFORCEMENT	SQ YD	1389	1389
44213100	PAVEMENT FABRIC	SQ YD	1034	1034
44213200	SAW CUTS	FOOT	7698	7698
44213204	TIE BARS 3/4"	EACH	154	154
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	16
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20
* 14 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	1041	1041

*Specialty Items

FILE NAME *	USER NAME = santacruz.je	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pvidat\santacruz.je\0388031\066079-sh1-deta1.dgn	DRAWN - _____	REVISED - _____	55			D3 PATCHING 2015-2	LIVINGSTON	15	3	
MODELNAME*	PLLOT SCALE * 500000.0018 ' / in.	CHECKED - _____	REVISED - _____			CONTRACT NO. 66D78				
	PLLOT DATE * 3/31/2014	DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT				
					SCALE: _____	SHEET 1 OF 2 SHEETS		STA. _____ TO STA. _____		