

EARTHWORK SCHEDULE						
STA	STA	EARTH EXCAVATION 25% SHRINKAGE (CU YD)	EMBANKMENT (FILL) (CU YD)	EARTHWORK BALANCE (CU YD)	EARTH EXCAVATION (CU YD)	
PRESTAGE						
95+11	99+65.5	132.1	0.0	132.1	176.2	
100+26.5	104+85	122.2	0.0	122.2	163.0	
STAGE TOTAL		254.4	0.0	254.4	339.2	
STAGE 1						
96+50	99+65.5	44.7	17.4	27.3	59.7	
100+26.5	103+50	42.5	26.8	15.7	56.7	
STAGE TOTAL		87.2	44.2	43.0	116.3	
STAGE 2						
96+50	99+65.5	34.5	28.3	6.2	46.0	
100+26.5	103+50	42.5	53.6	-11.1	56.7	
STAGE TOTAL		77.0	81.9	-4.9	102.7	
GRAND TOTAL		418.6	126.1	292.5	558.2	
USE					559.0	

TREE REMOVAL SCHEDULE		
STA	LT/RT	TREE REMOVAL (OVER 15 UNIT DIAMETER) UNIT
IL 29		
98+11.00	LT	24
98+68.00	LT	34
TOTALS		58.0
USE		58

TOPSOIL SCHEDULE				
STA	TO	STA	LT/RT	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH (SQ YD)
IL 29				
STAGE 1				
69+50.00		99+26.50	RT	245.4
100+62.50		103+50.00	LT	260.0
STAGE 2				
69+50.00		99+26.50	RT	278.8
100+62.50		103+50.00	LT	353.8
TOTALS				1138.0
USE				1138

RIPRAP A3 SCHEDULE					
STA	TO	STA	LT/RT	STONE RIPRAP, CLASS A3 (SQ YD)	FILTER FABRIC (SQ YD)
IL 29					
99+25.50		99+35.50	RT	17	17
99+25.50		99+35.50	LT	17	17
FROM STRUCTURE					829
TOTALS				33.3	862.3
USE				34	863

HMA SURFACE REMOVAL SCHEDULE				
STA	(FOR ONE ROAD) WIDTH (FOOT)	DEPTH NBL (INCH)	DEPTH SBL (INCH)	HMA SURFACE REMOVAL, VAR DEPTH NBL & SBL (SQ YD)
96+80.00	29	1.5	1.5	1607.9
97+00.00		1.5	1.5	
97+50.00		1.5	0.5	
98+00.00		1.5	0	
98+50.00		1.5	0	
99+00.00		1.5	0.25	
99+29.50	29	1.5	0.25	1659.4
100+62.50		1.5	0	
101+00.00		1.5	0	
101+50.00		1.5	0	
102+00.00		1.5	0	
102+50.00		1.5	0	
103+00.00	29	1.5	0.5	3267.3
103+20.00		1.5	1.5	
TOTALS				3267.3
USE				3268

DITCH CHECK SCHEDULE		
STA	LT/RT	TEMPORARY DITCH CHECKS (FOOT)
IL 29		
96+98.00	LT/RT	30
97+84.00	LT/RT	30
98+58.00	LT/RT	30
99+43.00	LT/RT	30
101+33.00	LT/RT	30
102+15.00	LT/RT	30
103+00.00	LT/RT	30
TOTALS		210.0
USE		210

REMOVAL SCHEDULE								
STA	TO	STA	LT/RT	LENGTH	WIDTH	HMA SURFACE REMOVAL - BUTT JOINT (SQ YD)	PAVEMENT REMOVAL (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)
96+50.00		96+80.00	RT/LT	30	29	193.3		
95+11.00		99+29.50	RT/LT	418.5	4			372.0
99+29.50		99+87.00	RT/LT	57.5	29		370.56	
100+05.00		100+62.50	RT/LT	57.5	29		370.56	
100+62.50		104+85.00	RT/LT	422.5	4			375.6
103+20.00		103+50.00	RT/LT	30	29	193.3		
TOTALS						386.7	741.1	747.6
USE						387	742	748

PERIMETER EROSION BARRIER SCHEDULE				
STA	STA	LT/RT	PERIMETER EROSION BARRIER (FOOT)	
IL 29				
96+50.00	103+50.00	RT	700	
96+50.00	103+50.00	LT	700	
TOTALS			1400.0	
USE			1400	

SEEDING SCHEDULE											
STA TO STA	LT / RT	AREA (SQ FT)	SEEDING, CLASS 2A (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 2 (ACRE)	EROSION CONTROL BLANKET (SQ YD)	TEMPORARY EROSION CONTROL SEEDING (POUND)		
96+50	99+65	RT	5,275	0.12	10.9	10.9	0.12	586.11	624		
96+50	99+65	LT	6,190	0.14	12.8	12.79	0.14	687.78	720		
100+26.5	103+50	LT	5,330	0.12	11	11.01	0.12	592.22	624		
100+26.5	103+50	RT	6,425	0.15	13.3	13.27	0.15	713.89	720		
TOTALS			0.53	48.0	48.0	48.0	0.53	2,580.0	2,688.0		
USE			0.6	48	48	48	0.6	2,580	2,700		



USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = *SCALE*	CHECKED -	REVISED -
PLOT DATE = *DATE* *TIME*	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(10B)BR	PEORIA	77	12
CONTRACT NO. 68481				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				