

GUARDRAIL SCHEDULE					
ITEM	LOCATION			QUANTITY	
TBT, TY 6	RT	99+07.35	99+51.10	1	2
	LT	100+39.90	100+83.65	1	
SPBGR, TY A, 6 FT POSTS	RT	99+07.35	98+57.35	50.0	112.5
	LT	100+83.65	101+46.20	62.5	
TBT, TY 1 SP TAN	RT	98+57.35	98+07.35	1	2
	LT	101+46.20	101+96.20	1	
GUARDRAIL REMOVAL	RT	98+29.60	100+14.50	185	408
	LT	99+68.30	101+91.60	223	
TERMINAL MARKER - DIRECT APPLIED	RT	98+07.35		1	2
	LT	101+96.20		1	
GUARDRAIL MARKERS, TY A	RT	98+13.00	100+41.50	4	8
	LT	99+80.50	101+91.50	4	

MISCELLANEOUS ITEMS SCHEDULE							
STA TO STA	ENGINEER'S FIELD OFFICE, TYPE A (CAL MO)	MOBILIZATION (L SUM)	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422 (EACH)	TRAFFIC CONTROL AND PROTECTION, STANDARD 701431 (SPECIAL) (EACH)	TRAFFIC CONTROL AND SURVEILLANCE (CAL DA)	CONSTRUCTION LAYOUT (L SUM)	CHANGEABLE MESSAGE SIGN (CAL MO)
<b>IL 29</b>							
JOBSITE	9.0	1.0	1.0	1.0	90.0	1.0	9.0
<b>TOTALS</b>	<b>9.0</b>	<b>1.0</b>	<b>1.0</b>	<b>1.0</b>	<b>90.0</b>	<b>1.0</b>	<b>9.0</b>
<b>USE</b>	<b>9</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>90</b>	<b>1</b>	<b>9</b>

GUARDRAIL AGG EROSION CONTROL SCHEDULE						
STA	TO	STA	LT/RT	WIDTH (FOOT)	GUARDRAIL AGGREGATE EROSION CONTROL (CU YD)	GUARDRAIL AGGREGATE EROSION CONTROL (TON)
<b>IL 29</b>						
98+07.40		99+51.10	RT	4	14.19	29.1
100+41.50		101+96.20	LT	4	15.28	31.3
<b>TOTALS</b>						<b>60.4</b>
<b>USE</b>						<b>61</b>

TEMPORARY RAMP SCHEDULE						
STA	TO	STA	LT/RT	LENGTH	WIDTH	TEMPORARY RAMP (SQ YD)
96+50.00		96+60.00	RT	10	29	32
96+50.00		96+60.00	LT	10	29	32
103+40.00		103+50.00	RT	10	29	32
103+40.00		103+50.00	LT	10	29	32
<b>TOTALS</b>						<b>128.9</b>
<b>USE</b>						<b>129</b>

PERMANENT SURVEY MARKER SCHEDULE			
STA	LT/RT	OFFSET FOOT	PERMANENT SURVEY MARKER, TYPE 1 EACH
100+25.83	RT	44.12	1
<b>TOTALS</b>			<b>1.0</b>
<b>USE</b>			<b>1</b>

INLET REMOVAL SCHEDULE		
STA	LT/RT	INLETS TO BE REMOVED (SPECIAL) EACH
104+31.00	LT/RT	1
<b>TOTALS</b>		<b>1.0</b>
<b>USE</b>		<b>1</b>