			URBAN	CONSTRUCTION CODE		
				PEORIA COUNTY 80% FED. 20% STATE	PEORIA COUNTY 0% FED. 100% STATE	PEORIA COUNTY 80% FED. 20% STATE
				ROADWAY	ROADWAY	BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0004	0011
						S.N. 072-0229
20200100	EARTH EXCAVATION	CU YD	2515	2515		
20200500	EARTH EXCAVATION (WIDENING)	CU YD	60	60		
20400100	BORROW EXCAVATION	CU YD	8595	8595		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7280	7280		
25000300	SEEDING, CLASS 3	ACRE	1.75	1.75		
25000350	SEEDING, CLASS 7	ACRE	3	3		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	277	277		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	277	277		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	277	277		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	6.1	6.1		
□ 25000750	MOWING	ACRE	2.25		2.25	
25100115	MULCH, METHOD 2	ACRE	4.5	4.5		
25100630	EROSION CONTROL BLANKET	SQ YD	4007	4007		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	2698	2698		

□ NON-PART. (100% STATE)

FILE NAME = P:\Projects\2008 Projects\00379 IL 8 over Kickapoo Creek\CV\CADD Sheets\0468697-sht-summary	USER NAME = bemery	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/20/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 8 OVER KICKAPOO CREEK

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1388	1Z-1D-BR-1IBR	PEORIA	89	4
		CONTRACT NO. 68697		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		