

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				URBAN		
				PEORIA COUNTY 80% FED. 20% STATE	PEORIA COUNTY 0% FED. 100% STATE	PEORIA COUNTY 80% FED. 20% STATE
				ROADWAY 0004	ROADWAY 0004	BRIDGE 0011 S.N. 072-0229
28000305	TEMPORARY DITCH CHECKS	FOOT	144	144		
28000400	PERIMETER EROSION BARRIER	FOOT	2862	2862		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28100109	STONE RIPRAP, CLASS A5	SQ YD	1179			1179
28200200	FILTER FABRIC	SQ YD	1179			1179
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	753	753		
35650300	BASE COURSE WIDENING 8"	SQ YD	753	753		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	864	864		
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	710	710		
40600952	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	611	611		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	922	922		
40603212	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	350	350		
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	263	263		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	45	45		

FILE NAME: P:\Projects\2008 Projects\00379 IL B over Kickapoo Creek\CADD Sheets\0468697.dwg	USER NAME: bmary	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 8 OVER KICKAPOO CREEK				F.A.S. RTE. 138B	SECTION (Z-10-BR-1)BR	COUNTY PEORIA	TOTAL SHEETS 89	SHEET NO. 5
PLOT SCALE: 1/8" = 100.0000' / in.	CHECKED: -	REVISED: -	SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 68697						
PLOT DATE: 3/20/2014	DATE: -	REVISED: -	FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT										