

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				PEORIA COUNTY 80% FED. 20% STATE	PEORIA COUNTY 0% FED. 100% STATE	PEORIA COUNTY 80% FED. 20% STATE
				ROADWAY 0004	ROADWAY 0004	BRIDGE 0011
						S.N. 072-0229
44000100	PAVEMENT REMOVAL	SQ YD	466	466		
44004250	PAVED SHOULDER REMOVAL	SQ YD	432	432		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	140	140		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2		
50105220	PIPE CULVERT REMOVAL	FOOT	158	158		
50200100	STRUCTURE EXCAVATION	CU YD	188			188
50300225	CONCRETE STRUCTURES	CU YD	208.7			208.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	432.5			432.5
50300260	BRIDGE DECK GROOVING	SQ YD	1392			1392
50300300	PROTECTIVE COAT	SQ YD	1817			1817
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	7902			7902
50800105	REINFORCEMENT BARS	POUND	12550			12550

FILE NAME = P:\Projects\2008 Projects\09379 IL 8 over Kickapoo Creek\CV\000 Sheets\0468097.dwg	USER NAME = bamery	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES IL 8 OVER KICKAPOO CREEK</b>				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	1388	12-10-BR-118R	PEORIA	89	6
PLOT DATE = 3/20/2014	DATE -	REVISED -					FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT				
									CONTRACT NO. 68697					