

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				PEORIA COUNTY 80% FED. 20% STATE	PEORIA COUNTY 0% FED. 100% STATE	PEORIA COUNTY 80% FED. 20% STATE
				ROADWAY 0004	ROADWAY 0004	BRIDGE 0011
						S.N. 072-0229
		URBAN				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	169240			169240
50800515	BAR SPLICERS	EACH	1700			1700
50800530	MECHANICAL SPLICERS	EACH	224			224
51201600	FURNISHING STEEL PILES HP12X53	FOOT	435			435
51202305	DRIVING PILES	FOOT	435			435
51203600	TEST PILE STEEL HP12X53	EACH	2			2
51500100	NAME PLATES	EACH	1			1
* 51603000	DRILLED SHAFT IN SOIL	CU YD	110.6			110.6
* 51604000	DRILLED SHAFT IN ROCK	CU YD	53.8			53.8
52000110	PREFORMED JOINT STRIP SEAL	FOOT	68.0			68.0
52100520	ANCHOR BOLTS, 1"	EACH	72			72
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	85	85		
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	110	110		
54213879	STEEL END SECTIONS 24"	EACH	2	2		

* SPECIALTY ITEM

FILE NAME :	USER NAME : barmy	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 8 OVER KICKAPOO CREEK	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
P:\Projects\2000 Projects\00379 IL 8	Kickapoo Creek\CV\4000 Sheets\048897-1	CHECKED -	REVISED -			1388	42-10-BR-1BR	PEORIA	89	7	
	PLOT SCALE = 100,0000' / 1" =	DATE -	REVISED -			CONTRACT NO. 68697		ILLINOIS FED. AID PROJECT			
	PLOT DATE = 3/20/2014					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.