CLASS A PATCH SCHEDULE							
LOCATION		CL A	CLA	CL A	CL A	SAW	TIE BARS
	REINF.	PATCH T1	PATCH T2	PATCH T3	PATCH T4	CUTS (FT)	3/4" (EA)
IL ROUTE 6 - IL 29 SPUR TO KNOXVILLE AVENUE							
NORTHBOUND DRIVING LANE	209.0		24.0	15.0	170.0	909.2	76
NORTHBOUND PASSING LANE	255.3		45.3	60.0	150.0	1110.6	143
SOUTHBOUND DRIVING LANE	212.7	4.0	58.7	40.0	110.0	925.2	124
SOUTHBOUND PASSING LANE	863.0	8.0	25.0	0.0	830.0	3754.1	708
SOUTHBOUND TRUCK LANE	32.0		16.0	16.0	0.0	139.2	0
IL ROUTE 6 - KNOXVILLE AVENUE TO ALLEN ROAD							
NORTHBOUND DRIVING LANE	206.7		20.7	16.0	170.0	899.1	65
NORTHBOUND PASSING LANE	68.7		38.7	30.0	0.0	298.8	0
SOUTHBOUND DRIVING LANE	8.0		8.0	0.0	0.0	34.8	0
SOUTHBOUND PASSING LANE	0.0		0.0	0.0	0.0	0.0	0
IL ROUTE 6 - ALLEN ROAD TO 20+00							
NORTHBOUND DRIVING LANE	248.3	16.0	110.0	52.3	70.0	1080.1	40
NORTHBOUND PASSING LANE	129.3		113.3	16.0	0.0	562.5	0
SOUTHBOUND DRIVING LANE	254.0	22.0	180.0	52.0	0.0	1104.9	0
SOUTHBOUND PASSING LANE	188.0	10.0	160.0	18.0	0.0	817.8	15
SUBTOTAL =	2675.0	60.0	799.7	315.3	1500.0	11636.3	1171
TOTALS =	2,680	60	800	315	1,500	11,650	1,175

LOCATION	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (EACH)	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 (EACH)	SPEED DISPLAY TRAILER* (CAL MO)	CHANGEABLE MESSAGE SIGN** (CAL DA)		
IL 6 NB/SB	2		3	21		
IL 6 NEAR RAMP AREAS		9				

- \* TWO SPEED DISPLAY TRAILERS (ONE FOR EACH DIRECTION OF TRAFFIC) FOR 1.5 CAL MO EACH SEE CONTRACT SPECIAL PROVISIONS
- \*\* THREE CHANGEABLE MESSAGE SIGNS FOR 7 CAL DAYS = 21 CAL DAYS

• 72-[(7,7-2,7-3)]-2;(6-1)[-3]

FI	LE NAME =	USER NAME = keithbr	DESIGNED	REVISED -			F.A.P.	SECTION	COUNTY TOTAL SHEET
68	BB76.dgn		DRAWN -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CCHEDITIE OF CHANTITIES	318	•	PEORIA 7 6
		PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -		SCHEDULE OF QUANTITIES	0.0		CONTRACT NO. 68B76
		PLOT DATE = 4/10/2014	DATE -	REVISED -				ILLINOIS FED. A	ID PROJECT