

LOCATION OF WORK:

FAI 39	FAI 39
NORTHBOUND RURAL	SOUTHBOUND RURAL
INTERSTATE	INTERSTATE
STA. 306+01 TO STA. 549+61	STA. 306+14 TO STA. 550+04
MCLEAN COUNTY	MCLEAN COUNTY
FUNDING BREAKOUT:	90% FEDERAL, 10% STATE
CONSTRUCTION TYPE CODE:	0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	50.0	30.0	20.0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	120.0	120.0	0.0
44213000	PATCHING REINFORCEMENT	SQ YD	610.0	380.0	230.0
44213200	SAW CUTS	FOOT	5,080.0	3,220.0	1,860.0
44213204	TIE BARS 3/4"	EACH	180.0	90.0	90.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	8,980.0	4,490.0	4,490.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	18,260.0	9,160.0	9,100.0
60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	17.0	9.0	8.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1,862.5	925.0	937.5
* 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	1,387.5	787.5	600.0
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4.0	2.0	2.0
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4.0	2.0	2.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	7.0	3.0	4.0
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7.0	3.0	4.0
* DENOTES SPECIALTY ITEM					