

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				90/10 FED/STATE ROADWAY	90/10 FED/STATE ROADWAY
				0005 URBAN	0021 URBAN
20200100	EARTH EXCAVATION	CU YD	1100		1100
20400800	FURNISHED EXCAVATION	CU YD	140		140
25000200	SEEDING, CLASS 2	ACRE	1.2		1.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108		108
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108		108
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108		108
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.4		2.4
25100115	MULCH, METHOD 2	ACRE	1.2		1.2
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	964		964
28000305	TEMPORARY DITCH CHECKS	FOOT	10		10
28000400	PERIMETER EROSION BARRIER	FOOT	2500		2500
28100803	STONE DUMPED RIPRAP, CLASS A2	TON	15		15
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	30		30
28200200	FILTER FABRIC	SQ YD	57		57

14

•RUTTING    •RAMP EXT

FILE NAME = c:\pwork\pwork\sparksge\0326237\067	USER NAME = sparksge	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
99-shr-509.dgn	PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISED -					55	(84-31)-4	SANGAMON	56	3
OnPoint	PLOT DATE = Oct-17-2013 09:54:05AM	DATE -	REVISED -		SCALE:	SHEET 2 OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 72F90			
ILLINOIS FED. AID PROJECT												